

- ThreeJs - Introduction
 - ⚡ Graphics processing
 - 🛠️ WebGL and Three JS
 - 🧳 What Can You Do with Three.js?
 - 🚀 Advantages
 - 💻 Installation
- Structure of Three.js App
 - 🌿 Core Components in Detail
 - 1. Scene
 - 2. Camera
 - 3. Renderer
 - 4. Geometry
 - 5. Material
 - 6. Mesh
 - 7. Lights
 - 8. Controls (Optional)
 - 9. Helpers (Optional)
 - 10. Animation Loop
 - 11. Loaders (For Models, Textures)
- 💻 Example Program (With Explanations Inside the code-block)
- Types of Geometry
 - 📦 Common Built-in Geometries (Primitives)
 - 📦 1. BoxGeometry
 - 🍊 2. SphereGeometry
 - 🍌 3. CircleGeometry
 - 🍩 4. TorusGeometry
 - 🔁 5. TorusKnotGeometry
 - 🏗️ 6. CylinderGeometry
 - 🍌 7. ConeGeometry
 - 🏠 8. PlaneGeometry
 - 💠 9. RingGeometry
 - 🌐 10. Platonic solid shapes.
 - A. TetrahedronGeometry
 - B. OctahedronGeometry
 - C. DodecahedronGeometry
 - D. IcosahedronGeometry
 - 🗑️ 11. LatheGeometry
 - 🍷 12. TubeGeometry

-  13. ShapeGeometry
-  14. ExtrudeGeometry
-  15. BufferGeometry
-  16. EdgesGeometry
-  17. WireframeGeometry
- THREE.LineSegments()
- THREE.LineBasicMaterial()
- THREE.LineDashedMaterial()
- THREE.Vector3()
 -  Usage Examples
 - Setting a position: `mesh.position = new THREE.Vector3(10, 0, -5);`
 - Direction vector: `const direction = new THREE.Vector3(1, 0, 0).normalize();`
 - Apply transformation: `v1.applyMatrix4(matrix); // Applies a transformation matrix`
- Perspective Camera and Field Of View (FOV) (Refer Note)
 -  In 3D Graphics (like Three.js):
 - FOV Range Of Values
 -  near – Near Clipping Plane
 -  far – Far Clipping Plane
 -  Clipping Planes and Depth Precision
 - Usual Values---- `const camera = new THREE.PerspectiveCamera(35, window.innerWidth/window.innerHeight, 0.1, 200);`
 -  Important Properties
 -  Methods
 -  Common Lifecycle Usage
 -  Example Usage
 - Camera Position
- Shape
 -  Basic Purpose:
 -  Syntax: `const shape = new THREE.Shape();`
 -  Example — Creating a Square Shape:
 -  Common Shape Methods:
 -  Use Cases:
- Line
 -  Purpose:
 -  Syntax:
 -  Example — Drawing a Simple Line Between Two Points:

-  Related Types:
-  Materials:
-  Use Cases:
- OrbitControls
 -  How to Use It
 -  Main Properties
 -  Events
 -  Mobile Support
 -  Typical Example Setup
 -  PROPERTIES
 -  PerspectiveCamera + screenSpacePanning: true
 -  OrthographicCamera
 -  METHODS (with description)
- Render Loop
 -  What is a Render Loop?
 -  Basic Structure of a Render Loop
 -  Why Use requestAnimationFrame()?
 -  DO NOT use setInterval() or setTimeout() or any selfcalling loops—they are less efficient and less smooth.
 -  Breakdown of What Happens in the Loop
 -  Time-Based Animation (Delta Time)
 -  Integration with OrbitControls
 -  Full Example
 -  `const clock = new THREE.Clock();`
 - `Renderer.SetPixelRatio`
- Clock
 -  Why not just use Date.now() or performance.now()?
 - Some Methods
 -  Use Case Example (delta-based rotation)
 -  Common Mistake to Avoid
- Orthographic Camera
 -  Real-World Analogy
 -  Use Cases
 -  Syntax in Three.js
 -  Example:
 -  Advantages
 -  Limitations
 -  Switching Cameras

-  Properties
-  Methods
-  Typical Usage
-  Summary Table
- Controls
 -  Commonly Used Three.js Controls
 - 1. OrbitControls
 - 2. TrackballControls
 -  Rotation Behavior:
 -  Quirks:
 - 3. FlyControls
 - 4. PointerLockControls
 -  What PointerLockControls does:
 -  What it does not do (by itself):
 - 5. FirstPersonControls
 - FlyControls vs FirstPersonControls
 -  Key Differences Explained
 -  Real-World Examples
 - 6. ArcballControls
 -  Characteristics:
 -  Rotation Behavior:
 -  Quirks:
 -  Real-World Examples
 - 7. MapControls
 -  Key Characteristics of MapControls
 -  Real-World Examples
 -  Summary Table
- Resizing
- Units in Three Js
 -  1. Units Are Arbitrary but Consistent
 -  2. Units and the Camera
 -  3. Light Intensity, Distance, and Units
 -  4. Real-World Scale Reference
 -  5. Physics Engines (like Cannon.js, Ammo.js)
 -  Summary
- Helpers
 -  1. AxesHelper
 -  2. GridHelper

-  3. CameraHelper
-  4. DirectionalLightHelper
-  5. PointLightHelper
-  6. SpotLightHelper
-  7. HemisphereLightHelper
-  8. BoxHelper
-  9. Box3Helper
-  10. SkeletonHelper
-  11. PlaneHelper
-  Updating Helpers
-  Summary Table
- Object3D
 -  What is Object3D?
 -  Constructor
 -  Key Properties
 -  Key Methods
 -  Transformation
 -  Real-Life Analogy
 -  Usage Examples
 - Grouping Objects
 - Empty Parent for Rotation
 - .position
 - .scale
 -  Tip
 - Example-
- Vector3 - II
 - .position.x, .position.y , .position.z --- Written above inside Object3D topic
 - .distanceTo()
- Group
 - Example
 -  When to use which?
- Scene Hierarchy
 - EXAMPLE---
 - Another Example--
 -  6. Traversing the Graph
 - object.material.wireframe = true;
 -  Common Classes in the Hierarchy
 -  5. Why This Matters

- Euler

-  1. What is an Euler rotation?
-  2. Constructor Syntax
-  3. Common Rotation Orders
-  4. Properties
-  5. Methods
-  6. Example Usage
-  7. Gimbal Lock
-  8. Euler vs Quaternion

- Animations

-  1. Types of Animation in Three.js
-  2. Basic Animation Loop
-  3. Using THREE.Clock
-  4. AnimationMixer for glTF / FBX animations
-  5. External Animation Libraries (Optional)
-  6. Helper: .matrixAutoUpdate
-  Animation Targets
-  Best Practices

- BufferGeometry - 2

-  What is BufferGeometry?
-  2. Anatomy of BufferGeometry
- BufferAttribute
 -  What is BufferAttribute?
 - Important Properties of BufferAttribute
 -  Useful Methods of BufferAttribute
 - Dynamic BufferAttributes
-  Common Attributes
-  Useful Methods
-  Example — Triangle
-  Example: Custom Geometry with position, normal, and color:
-  Built-in Geometries use BufferGeometry
-  8. When to use?

- Materials vs texture

-  Materials — The "Skin" of 3D Objects
-  Textures — The "Paint" on Materials
-  Relationship Summary
-  Real-Life Analogy

- Materials

-  Common Material Types
-  Important Material Properties
 - .side
 - .fog [See FOG for more details]
-  Common Material Methods
-  Special Maps Used in Materials
-  Common Usage Example
-  Choosing the Right Material
-  Modifying Material at Runtime
-  Disposing Materials
- Color
 -  THREE.Color — Overview
 -  Creating a Color
 -  Properties
 -  Common Methods
 -  Examples:
 -  Setting Color in Material
 -  Example: Interpolating Between Two Colors
 -  Tip: Color Conversion
 -  When to Use THREE.Color
- Fog
 -  Constructor Syntax
 -  Example:
 -  Properties
 -  Methods
 -  How It Works
 -  Live Scene Example
- MeshLambertMaterial
 -  Constructor
 -  Visual Character
 -  Common Parameters
 -  Example:
 -  Methods
 -  Lighting Behavior
 -  Real-world Usage
- MeshPhongMaterial
 -  Constructor
 -  Key Features

-  Common Properties
-  Lighting Behavior
-  Example
-  Related Materials
 -  Methods
 -  Real-World Use Cases
- Pane (From UI library- TweakPane)
 -  Features of Pane:
 - Example Use Case:
 -  Why params?
 -  Use Case : Controlling a rotating cube's position, visibility, and rotation speed
- MeshStandardMaterial
 -  THREE.MeshStandardMaterial — In Detail
 -  When to use:
 -  Constructor Syntax:
 -  Key Properties:
 -  Supported Maps:
 -  Important Notes:
 -  Example:
 -  MeshStandardMaterial vs MeshPhongMaterial:
- MeshPhysicalMaterial
 -  Basic Syntax:
 -  Additional Properties (Only in MeshPhysicalMaterial):
 -  Example Use: Simulating Glass
 -  Other Example: Car Paint with Clearcoat
 -  Texture Maps It Supports:
 -  Tips:
 -  Differences vs MeshStandardMaterial:
- Scene - 2
 -  THREE.Scene — Properties
 -  Inherited from Object3D
 -  THREE.Scene — Methods
 -  Example:
 -  Advanced Usage:
- Loading Texture
 -  Syntax
 -  Constructor

-  Properties
-  Methods
-  Common Use Case Example
-  Prepending Path
-  With LoadingManager
-  Notes
-  Supported Image Formats
- Combinations

ThreeJs - Introduction

Three.js is a **JavaScript 3D library** that makes it easy to create and display animated 3D graphics in the browser using **WebGL** .

-- A high-level JavaScript library for creating and displaying 3D graphics in web browsers

-- Simplifies 3D graphics creation and animation (models, particle systems, lights, cameras) without low-level WebGL code knowledge

What is WebGL?

WebGL (Web Graphics Library) is a low-level API for rendering 2D and 3D graphics in web browsers without using plugins. However, it's complex and hard to write from scratch — that's where Three.js comes in.

Its a way to communicate with the GPU

What is Three.js?

Three.js is a higher-level library built on top of WebGL. It simplifies 3D rendering, so you can create scenes, objects, lights, and cameras more easily.

Graphics processing

What is graphics processing?

- The process of rendering 3D graphics on a computer screen in  **real-time**  which is interactive. For example it should not be like a recorded or created video
- Requires millions of calculations per second for just a basic graphics

Why is it complex?

- The computer needs to know information like the position, color, and location of every vertex of an object
- There is a piece of instruction needed for each pixel on the screen

-- Because it is so complex and sophisticated and so much processing happening, we invented GPU

What is a GPU?

- Stands for Graphics Processing Unit
- A special type of hardware that can run simple calculations in parallel
- Designed to handle the demands of rendering 3D graphics

WebGL and Three JS

- WebGL provides a language to talk to the GPU and instruct it on what to render
- WebGL is a JavaScript API for rendering 3D graphics in a web browser using the GPU
- It very complex and takes lot of time to really communicate with and program with

Three.js is built on top of WebGL and implements it under the hood

Three.js abstracts the complicated WebGL language into an easy-to-use JavaScript API allowing for creative focus on projects

What Can You Do with Three.js?

- Create interactive 3D websites or apps
- Build games
- Visualize data in 3D
- Make VR/AR experiences
- Animate 3D models (using GLTF, FBX, etc.)

Advantages

- Abstracts complex WebGL code
- Cross-browser compatible
- Large community and many plugins
- Supports lights, shadows, textures, physics engines, etc.


Installation

```
npm install three
```


Structure of Three.js App

Three.js Fundamentals

Structure of a Three.js App



Scene Graph



✖ Core Components in Detail

1. Scene

A container that holds all 3D objects, lights, and cameras. Think of it like a stage-- Eg-

```
const scene = new THREE.Scene();
```

Scene itself is a 3D object as well.

2. Camera

Defines what part of the scene is visible. The most common one is the

`PerspectiveCamera`.

Eg- `const camera = new THREE.PerspectiveCamera(fov, aspect, near, far);`

Common Camera Types:

- `THREE.PerspectiveCamera`: Like a real-world camera (with FOV).
- `THREE.OrthographicCamera`: For 2D-like rendering without perspective distortion.

3. Renderer

Takes the scene and camera and draws the result to the screen.

Analogy would be some images being shown in 24 fps or 60 fps, etc so as to create a motion picture or a movie. In the same way renderer would be called for like 60 times/sec, etc

```
const renderer = new THREE.WebGLRenderer({ antialias: true });
renderer.setSize(window.innerWidth, window.innerHeight);
document.body.appendChild(renderer.domElement);
```

What is Anti-Aliasing?

Aliasing happens when diagonal or curved edges in your 3D models look jagged or pixelated (staircase like sharp-edges), especially at lower resolutions or when we are rotating the object. With hardware using high resolution or pixel ratio monitor, one can avoid that.

Anti-aliasing is a graphics technique used to reduce that effect by blending edge pixels with fader color like gradient to make the lines appear smoother.

Without anti-aliasing:

- Edges look rough and stair-stepped.

With anti-aliasing (`antialias: true`):

- Edges are smoother and more visually appealing.

Should You Always Use It?

-  **Yes** , if you're building for modern devices and want **better visual quality** .

-  **Be cautious** on low-performance or mobile devices, as it can slightly impact performance.

renderer.setPixelRatio

```
renderer.setPixelRatio(Math.min(window.devicePixelRatio, 2))
```

`renderer.setPixelRatio` may work as an Antialiasing strategy (Not for every device) because by default value would be less than 1 or 1. So by above code if at all the pixel ratio is 2 or more one can use the above code to exploit the more pixel ratio that the monitor has.

You don't want to use the max pixel ratio to avoid cpu usage hence, `Math.min()`

4. Geometry

Defines the **shape** of a 3D object.

Examples:

- `BoxGeometry`, `SphereGeometry`, `PlaneGeometry`, `BufferGeometry`

Eg- `const geometry = new THREE.BoxGeometry(1, 1, 1);`

5. Material

Defines how the surface of the object looks.

Examples:

- `MeshBasicMaterial`: Unlit, flat color
- `MeshStandardMaterial`: Supports lighting
- `MeshPhongMaterial`, `MeshLambertMaterial`, etc.

Eg- `const material = new THREE.MeshStandardMaterial({ color: 0xff0000 });`

6. Mesh

Combines a geometry and a material into a renderable object.

```
const mesh = new THREE.Mesh(geometry, material);
scene.add(mesh);
```

One can always change the position of mesh by `mesh.position.set(x, y, z)` or for example-- `mesh.position.x = 5`

7. Lights

Illuminate the scene. Some materials (like `MeshStandardMaterial`) require light to be visible.

Adds realism by simulating light and shadows.

Common light types:

- `AmbientLight`: Uniform light with no direction
- `PointLight`: Emits light in all directions from a point
- `DirectionalLight`: Sun-like light from a direction

```
const light = new THREE.PointLight(0xffffff, 1);
scene.add(light);
```

8. Controls (Optional)

Allow user interaction like rotating, panning, or zooming.

```
import { OrbitControls } from 'three/examples/jsm/controls/OrbitControls.js';
const controls = new OrbitControls(camera, renderer.domElement);
```

9. Helpers (Optional)

Visual aids for debugging or layout.

Examples:

- [AxesHelper](#), [GridHelper](#), [CameraHelper](#)

```
const gridHelper = new THREE.GridHelper(10, 10);
scene.add(gridHelper);
```

10. Animation Loop

Continuously updates and renders the scene.

```
function animate() {
  requestAnimationFrame(animate);
  mesh.rotation.y += 0.01;
  renderer.render(scene, camera);
}
animate();
```

11. Loaders (For Models, Textures)

Load external assets:

- [GLTFLoader](#), [OBJLoader](#) for 3D models
- [TextureLoader](#) for image textures

```
const loader = new THREE.TextureLoader();
const texture = loader.load('path/to/image.jpg');
```

Children of a parent inherits the transformational property of the parent

Example Program (With Explanations Inside the code-block)

This Three.js code is a **minimal setup to render a red cube on the screen** using a 3D scene.

```
import * as THREE from "three";

// initialize the scene
const scene = new THREE.Scene();
  //-----> The scene is like a container that holds all objects (meshes, lights,
  cameras). Think of it as your virtual 3D world.

// add objects to the scene
const cubeGeometry = new THREE.BoxGeometry(1, 1, 1);
  //-----> This creates a box (1x1x1 units). It's a set of vertices and
  faces.

const cubeMaterial = new THREE.MeshBasicMaterial({ color: "red" });
  //-----> A material defines how the surface of a shape looks. MeshBasicMaterial is
  a simple unlit material(no lighting effects).

const cubeMesh = new THREE.Mesh(cubeGeometry, cubeMaterial); // Mesh = Geometry +
Material.

scene.add(cubeMesh); // You add it to the scene to make it visible in rendering.

// initialize the camera
const camera = new THREE.PerspectiveCamera(
  75,
  window.innerWidth / window.innerHeight, // for aspect ratio
  0.1,
  30
); //-----> This creates a perspective camera, which mimics human eye perception.
      75 = Field of view (FOV).
      aspect ratio = important to avoid stretching.
      0.1 = near clipping plane (anything closer won't show).
      30 = far clipping plane.

camera.position.z = 5; //---> Move the camera 5 units away from the cube on the Z-
axis so we can see it.

// HERE-- if written scene.add(camera), will give you a different experience since
camera is also a 3D object like for animating the camera like a scene object or
parenting it.

// initialize the renderer
const canvas = document.querySelector("canvas.threejs");
const renderer = new THREE.WebGLRenderer({
  canvas: canvas,
}); //-----> Creates the WebGL renderer which converts your 3D scene
into pixels and draws it on the canvas.
renderer.setSize(window.innerWidth, window.innerHeight); //-----> Makes sure the
canvas matches the full window size.
renderer.render(scene, camera) //-----> This actually draws the scene from the
perspective of the camera.
```

Types of Geometry

In **Three.js**, geometries define the **shape** of 3D objects. There are many built-in geometry types for common shapes. Here's a categorized list:

Common Built-in Geometries (Primitives)

1. PlaneGeometry
2. BoxGeometry
3. CircleGeometry
4. RingGeometry
5. SphereGeometry
6. TubeGeometry
7. TorusGeometry
8. TorusKnotGeometry
9. CylinderGeometry
10. ConeGeometry
11. LatheGeometry
12. Platonic solid shapes TetrahedronGeometry, OctahedronGeometry, DodecahedronGeometry, IcosahedronGeometry
13. ShapeGeometry
14. ExtrudeGeometry
15. EdgesGeometry
16. WireframeGeometry
17. BufferGeometry

1. BoxGeometry

A cube or rectangular box. SYNTAX- `new THREE.BoxGeometry(width, height, depth, );`

SYNTAX

```
new THREE.BoxGeometry(  
  width,
```

```
height,  
depth,  
widthSegments = 1,    // Horizontal segments (subdivisions along width)  
heightSegments = 1    // Vertical segments (subdivisions along height)  
depthSegments = 1    // Vertical segments (subdivisions along depth)  
);
```

2. SphereGeometry

A full 3D sphere (e.g., for planets or balls).

SYNTAX

```
new THREE.SphereGeometry(  
  radius,  
  widthSegments,  
  heightSegments,  
  phiStart,  
  phiLength,  
  thetaStart,  
  thetaLength  
);
```

✓ widthSegments

- Number of **vertical segments** (like the segments of an orange).
- These go **around** the sphere (longitude).
- Minimum: 3.
- As you decrease, it looks more of 3d triangle-circle type, esp at 3(min)

✓ heightSegments

- Number of **horizontal segments** (like layers of a cake).
- These go **from top to bottom** (latitude).
- Minimum: 2.
- As you decrease, it looks more of 3d rectangle-cone type, esp at 3(min)

⚠ Performance Note

- **Higher segments** = smoother look, but **more vertices** = heavier to render.
- Use **low segments for previews** , higher for final rendering.

For phiStart, phiLength, thetaStart and thetaLength, lets see some analogies--

Analogy: Slicing a Globe

Imagine you're working with a **world globe** and you're painting or cutting sections of it:

Parameter	Analogy on a Globe	What It Does
<code>phiStart</code>	Start turning the globe sideways	The starting longitude of the cut
<code>phiLength</code>	How much you rotate the globe sideways	The longitude sweep (side-to-side width)
<code>thetaStart</code>	Start slicing from the North Pole	Where to start from top to bottom
<code>thetaLength</code>	How far down toward the South Pole you go	The latitude sweep (vertical height)

Analogy: Cutting a Layer Cake

Now imagine a tall, round cake:

Parameter	Analogy with Cake	What It Means
<code>phiStart</code>	Where you put your knife on the side	Starting angle around the cake
<code>phiLength</code>	How wide you slice it (side to side)	Width of the slice you cut around
<code>thetaStart</code>	If you slice only the top part	Start from the top of the cake
<code>thetaLength</code>	How far down you cut (not all the way)	How much vertical height to keep

You can write the angles in terms of `Math.Pi`

Eg- `phiStart- 0` and `phiLength- Math.Pi` will give you half cut sphere from left to right

Eg- `thetaStart- 0` and `thetaLength- Math.Pi/2` will give you half cut sphere from top to bottom

3. Circle Geometry

A flat 2D circle in the XY plane.

SYNTAX--

```
new THREE.CircleGeometry(  
  radius = 1,           // Radius of the circle  
  segments = 8,         // Number of triangle segments (sides)  
  thetaStart = 0,       // Starting angle in radians  
  thetaLength = Math.PI * 2 // Central angle (how much of the circle to draw)  
)
```

segments refers to how **finely subdivided** the geometry is — i.e., **how many sections or divisions are used** to construct the shape.

🔍 What "segments" actually means:

Segments are like the **number of lines or faces** used to form a curve or surface.

More segments → smoother, rounder shape

Fewer segments → blockier, low-poly look, 2d triangle look

4. TorusGeometry

A donut shape.

SYNTAX--

```
new THREE.TorusGeometry(  
  radius,           // Major radius (distance from center to tube center)  
  tube,            // Minor radius (thickness of the tube)  
  radialSegments,   // Number of segments around the cross-section  
  tubularSegments,  // Number of segments around the torus ring  
  arc = Math.PI * 2 // How much of the ring to create (default = full circle)  
);
```

✅ 1. **tubularSegments** ( around the **main ring**)

- Think of **how many steps you take to go around the donut** .
- It controls the smoothness **around the big circle** (the major radius).

More tubularSegments = smoother outer ring.

🧠 Think of it as:

“How many slices do I divide the whole donut into around its hole?”

✓ 2. `radialSegments` (🔄 around the **tube**)

- Think of **how round the tube** 📏 **cross-section** 📏 is .
- It controls the smoothness of the **tube thickness** .

More radialSegments = rounder tube.

🧠 Think of it as:


“How round is the pipe that forms the donut?”

🔄 5. TorusKnotGeometry

A twisted knot in torus form.

SYNTAX--

```
new THREE.TorusKnotGeometry(  
  radius = 1,           // Major radius (distance from center to tube center)  
  tube = 0.4,           // Minor radius (thickness of the tube)  
  tubularSegments = 64, // How many segments along the knot path  
  radialSegments = 8,   // How round the tube is  
  p = 2,                // Number of times the geometry winds around its axis  
(longitudinally)  
  q = 3                 // Number of times the geometry winds around a circle in  
the interior (latitudinally)  
)
```



6. CylinderGeometry

A cylinder or cone.

SYNTAX--

```
new THREE.CylinderGeometry(  
  radiusTop = 1,           // Radius of the cylinder at the top  
  radiusBottom = 1,        // Radius at the bottom  
  height = 1,              // Height of the cylinder  
  radialSegments = 8,      // Number of segmented faces around the circumference  
  heightSegments = 1,      // Number of rows of faces along the height  
  openEnded = false,       // Whether the ends are capped (true = open)  
  thetaStart = 0,          // Start angle for first segment (in radians)  
  thetaLength = Math.PI * 2 // The central angle, often full circle (2π)  
)
```

7. ConeGeometry

A cone (just like a cylinder but radiusTop is 0).

```
new THREE.ConeGeometry(  
  radius = 1,              // Radius of the base of the cone  
  height = 1,              // Height of the cone  
  radialSegments = 8,      // Number of segmented faces around the circumference
```

```

heightSegments = 1,    // Number of segmented faces along the height
openEnded = false,     // Whether the base is open (true = no cap)
thetaStart = 0,        // Starting angle in radians
thetaLength = Math.PI * 2 // Central angle (how much of the circle is swept)
)

```

8. PlaneGeometry


A 2D flat plane (e.g., ground or screen).

SYNTAX--

```

new THREE.PlaneGeometry(
  width = 1,           // Width of the plane
  height = 1,          // Height of the plane
  widthSegments = 1,   // Horizontal segments (subdivisions along width)
  heightSegments = 1   // Vertical segments (subdivisions along height)
)

```




9. RingGeometry

A ring or donut-like 2D shape. Looks like a Toa octagon type

A ring or disc with a hole in the center, like a washer or halo.

SYNTAX--

```
new THREE.RingGeometry(  
  innerRadius = 0.5,           // Radius of the hole in the center  
  outerRadius = 1,             // Outer radius of the actual solid part of ring  
  thetaSegments = 8,          // Number of segments around the circumference, actual  
  edges, hence no of edges inc/dec  
  phiSegments = 1,            // Number of segments along the radial direction, on  
  the solid surface  
  thetaStart = 0,              // Starting angle in radians (default = 0)  
  thetaLength = Math.PI * 2    // Central angle of the ring sweep (default = full  
  circle)  
)
```



10. Platonic solid shapes.


A.TetrahedronGeometry

- Only 4 triangular faces — the simplest polyhedron.
- **detail** can be used to subdivide and smooth. Setting this to a value greater than 0 adds vertices making it no longer a tetrahedron, making at max a kind of sphere

SYNTAX--

```
new THREE.TetrahedronGeometry(  
  radius = 1,
```

```
    detail = 0  
  )
```




B. OctahedronGeometry

- 8 triangular faces — like two pyramids stuck base-to-base.
- `detail` smooths it toward a sphere-like shape. Default is 0. Setting this to a value greater than zero add vertices making it no longer an octahedron.

SYNTAX--

```
new THREE.OctahedronGeometry(  
  radius = 1,  
  detail = 0  
)
```


D. IcosahedronGeometry

- A 20-faced polyhedron, each face is an equilateral triangle.
- Often used as a base for spherical meshes (e.g., for planets or balls).
- Higher **detail** = more spherical shape. Default is 0. Setting this to a value greater than 0 adds more vertices making it no longer an icosahedron. When detail is greater than 1, it's effectively a sphere.

SYNTAX--

```
new THREE.IcosahedronGeometry(  
  radius = 1,  
  detail = 0  
)
```

▼ Controls		
▼ THREE.IcosahedronGeometry		
radius	10	10
detail	0	0



Open in New Window


11. LatheGeometry

Creates a shape by rotating points (like pottery).

-- This geometry is used to create **rotationally symmetrical shapes** by spinning a set of 2D points around the Y-axis — like pottery made on a wheel.

SYNTAX--

```
new THREE.LatheGeometry(
  points,           // Array of Vector2 points (shape outline)
  segments = 12,    // Number of rotational segments
  phiStart = 0,     // Starting angle in radians (default = 0)
  phiLength = 2 * Math.PI // How much of the circle to sweep (default = full 360°)
)
```



12. TubeGeometry

Creates a 3D shape along a path/curve.

- This geometry creates a **tube-shaped mesh** that follows a custom 3D path — like a pipe, roller coaster, or wire.


"2" Shaped

SYNTAX--

```
new THREE.TubeGeometry(  
  path,           // A THREE.Curve instance that defines the center line of the  
  tube  
  tubularSegments, // Number of segments along the tube  
  radius,          // Radius of the tube  
  radialSegments,  // Number of segments around the circumference  
  closed           // Boolean indicating whether the tube is closed into a loop  
)
```

Parameter	Type	Description
path	THREE.Curve	The 3D curve path that defines the tube's central spine

Parameter	Type	Description
<code>tubularSegments</code>	<code>Integer</code> (default 64)	Number of segments along the length of the tube
<code>radius</code>	<code>Float</code> (default 1)	Radius of the tube
<code>radialSegments</code>	<code>Integer</code> (default 8)	Number of segments around the circumference of the tube
<code>closed</code>	<code>Boolean</code> (default false)	If true, connects the start and end of the tube to form a loop



13. ShapeGeometry

- Is used to generate **2D extruded** flat geometry from one or more custom shapes (made of paths). It's useful for rendering flat icons, cutouts, and custom 2D designs.

SYNTAX--

```
new THREE.ShapeGeometry(
  shapes,           // Shape or array of Shapes (THREE.Shape or [THREE.Shape])
  curveSegments = 12 // Number of segments per curve (resolution/smoothness)
)
```

Parameter	Type	Description
<code>shapes</code>	<code>THREE.Shape</code> or <code>THREE.Shape[]</code>	The shape(s) to convert to geometry — must be paths defined in 2D
<code>curveSegments</code>	<code>Integer</code> (default: 12)	Number of segments per Bézier curve or arc (higher = smoother curves)

Example

```
const shape = new THREE.Shape();
shape.moveTo(0, 0);
shape.lineTo(0, 10);
shape.lineTo(10, 10);
shape.lineTo(10, 0);
shape.lineTo(0, 0);

const geometry = new THREE.ShapeGeometry(shape, 24);
```

This creates a flat square shape geometry with high curve smoothness (though in this case it's just straight lines).

Tip

- `THREE.Shape` is created using path commands (`lineTo`, `bezierCurveTo`, `absarc`, etc.).
- You can also use `holes` in shapes (e.g. for making a donut-like ring with a cutout).

14. ExtrudeGeometry

- Turns a 2D shape into 3D by extruding it.
- This geometry allows you to **extrude a 2D shape into 3D** — perfect for 3D text, logos, or custom objects like walls, gears, and more.

SYNTAX--

```
new THREE.ExtrudeGeometry(
  shapes,          // A Shape or array of Shapes
  options          // Object containing extrusion settings
)
```

Parameters

1. `shapes`

Type: `THREE.Shape` or `THREE.Shape[]`

Description: The 2D shape(s) you want to extrude into 3D. Can include holes.

2. `options` (optional)

Type: `Object`

Description: Configuration object for controlling the extrusion behavior.

Full `options` Object

Option	Type	Default	Description
<code>depth</code>	Number	1	How far to extrude the shape (Z direction)
<code>bevelEnabled</code>	Boolean	true	Whether to enable beveling
<code>bevelThickness</code>	Number	0.2	How deep the bevel goes
<code>bevelSize</code>	Number	0.1	How far the bevel extends from shape outline
<code>bevelOffset</code>	Number	0	Distance the bevel starts inset from the edge
<code>bevelSegments</code>	Integer	3	Number of segments in the bevel curve
<code>curveSegments</code>	Integer	12	Number of segments per curve (for round corners)
<code>steps</code>	Integer	1	Number of steps (layers) along the depth
<code>extrudePath</code>	CurvePath	undefined	A 3D curve path to extrude along instead of straight Z
<code>UVGenerator</code>	Object	Internal	Custom UV mapping logic (rarely used manually)

Example

```

const shape = new THREE.Shape();
// Draw a square
shape.moveTo(0, 0);
shape.lineTo(0, 5);
shape.lineTo(5, 5);
shape.lineTo(5, 0);
shape.lineTo(0, 0);

const extrudeSettings = {
  steps: 2,
  depth: 10,
  bevelEnabled: true,
  bevelThickness: 1,
  bevelSize: 0.5,
  bevelSegments: 5
};

const geometry = new THREE.ExtrudeGeometry(shape, extrudeSettings);

```

Use Cases

- 3D logos and text
- Mechanical parts like gears and tracks
- Complex architectural features
- Paths extruded along a curve (e.g., railings, pipes, tracks)

15. BufferGeometry

- The base class for all geometries. It's used for custom or advanced shapes.
- It is a **foundational class** in Three.js used to construct and manage **custom geometries** by defining raw buffer data (positions, normals, uvs, etc.).

Unlike predefined geometries like **BoxGeometry**, **BufferGeometry** gives you **low-level control** over the structure of your mesh.

SYNTAX--- `const geometry = new THREE.BufferGeometry();`

Unlike other geometries, it takes **no constructor arguments** , but you manually define attributes and index later.

[BUFFER GEOMETRY - 2]

16. EdgesGeometry

Generates **an outline of the visible edges** of a geometry — like the **edges of polygons** , useful for clean outlines or wireframe effects.

SYNTAX--- `const edges = new THREE.EdgesGeometry(geometry, thresholdAngle);`

Parameter	Type	Default	Description
<code>geometry</code>	Geometry or BufferGeometry	Required	The geometry you want to outline
<code>thresholdAngle</code>	Number	1	Angle in degrees. Edges are shown only if the angle between face normals is greater than this .

Example: Use a low angle like **1** to only get sharp edges; a higher angle like **90** will include softer edges.

Example

```
const box = new THREE.BoxGeometry(1, 1, 1);
const edges = new THREE.EdgesGeometry(box, 30);
const line = new THREE.LineSegments(edges, new THREE.LineBasicMaterial({ color: 0xffffffff }));
scene.add(line);
```

HERE-- `const edges = new THREE.EdgesGeometry(box, 30);`

- `EdgesGeometry` extracts **only the visible and sharp edges** of the `box` geometry.
- The second argument `30` is the **threshold angle in degrees** .
 - **What it means** : If the angle between the normals of two adjacent faces is **greater than 30°** , an edge between them will be included.
 - For a cube (which has 90° angles at corners), this will result in all outer edges being included — essentially outlining the box.

```
const line = new THREE.LineSegments(edges, new THREE.LineBasicMaterial({ color: 0xffffffff }));
```

- `LineSegments` is used to draw **disconnected straight lines** between vertex pairs (edges).
- `edges` contains the geometry of those line segments.

- `LineBasicMaterial` is a basic material used to define the color (white in this case) of the lines.

Summary

Component	What it does
<code>BoxGeometry</code>	Creates the cube shape
<code>EdgesGeometry</code>	Extracts visible, sharp edges
<code>LineSegments</code>	Turns those edges into drawable line pairs
<code>LineBasicMaterial</code>	Styles the lines (color, etc.)
<code>scene.add</code>	Adds the wireframe box outline to the scene

Use Case

- Highlighting sharp edges (like corners of a cube)
- Stylized outlines or hidden line rendering
- Clean non-overlapping wireframes

◆ 17. WireframeGeometry

Creates a **full wireframe representation** of a geometry — showing **all edges** , regardless of angle. More like what you see in 3D modeling tools.

SYNTAX-- `const wireframe = new THREE.WireframeGeometry(geometry);`

Example

```
const sphere = new THREE.SphereGeometry(1, 8, 8);
const wireframe = new THREE.WireframeGeometry(sphere);
const line = new THREE.LineSegments(wireframe, new THREE.LineBasicMaterial({ color: 0x00ff00 }));
scene.add(line);
```

HERE--

`THREE.WireframeGeometry(geometry)`

- Converts the `sphere` geometry into a **wireframe** version.

- **Shows all edges** (not just sharp ones like `EdgesGeometry`).
- Returns a new geometry with **line segments connecting vertices** across all faces.

✅ Use Case

- Full mesh wireframes (for debugging or style)
- Visualizing geometry topology (e.g., all triangles)
- Creating "X-ray" or transparent mesh effects

THREE.LineSegments()

This class draws **independent pairs of points** as line segments — perfect for rendering **edges**, **wireframes**, or disconnected lines.

SYNTAX--- `const lineSegments = new THREE.LineSegments(geometry, material);`

Parameter	Type	Description
<code>geometry</code>	<code>THREE.BufferGeometry</code> or <code>THREE.Geometry</code>	The shape data: vertices that define the lines. Every pair of vertices becomes a line segment.
<code>material</code>	<code>THREE.LineBasicMaterial</code> or <code>THREE.LineDashedMaterial</code>	Defines how the line looks: color, width, dash pattern, etc.

🧠 How It Works

- The geometry must contain a list of vertices.
- Every **two consecutive vertices** are connected into one line segment.
- For example, vertices `[A, B, C, D, E, F]` will draw line segments:
 - `A → B`
 - `C → D`
 - `E → F`

This is **different from** `THREE.Line()`, which connects vertices **in order** like a polyline.

🔗 Usage Example

```
const geometry = new THREE.BufferGeometry();
const points = [
  new THREE.Vector3(0, 0, 0),
  new THREE.Vector3(1, 0, 0), // line 1
  new THREE.Vector3(0, 1, 0),
  new THREE.Vector3(1, 1, 0), // line 2
];
geometry.setFromPoints(points);

const material = new THREE.LineBasicMaterial({ color: 0xff0000 });
const lines = new THREE.LineSegments(geometry, material);
scene.add(lines);
```

Here `.setFromPoints()` **creates a geometry** (usually a line or shape) by connecting a series of 3D points (or `Vector3s`).

- The `.setFromPoints()` method is used in **Three.js** with geometry classes like `THREE.BufferGeometry` or `THREE.LineGeometry` to create geometry **from a list of points** .
- SYNTAX--- `geometry.setFromPoints(pointsArray);` *Here

Material Options

You can use:

- `LineBasicMaterial`: solid lines
- `LineDashedMaterial`: dashed lines (needs `computeLineDistances()` called on geometry)

Extra Info

You can also create a custom subclass if you want more control, but `LineSegments` works out of the box for:

- `EdgesGeometry`
- `WireframeGeometry`
- Custom point pairs

THREE.LineBasicMaterial()

A material for drawing **simple flat-colored lines** . It **does not react to lights** , meaning it stays the same color regardless of the scene's lighting setup.

SYNTAX--

```
const material = new THREE.LineBasicMaterial({
  color: 0xff0000,
  linewidth: 2,
  linecap: 'round',
  linejoin: 'round',
});
```

Parameter	Type	Default	Description
color	Color	0xffffffff	The color of the line. Can be hex (0xff0000), CSS color ('red'), or THREE.Color.
linewidth	Number	1	Width of the line. Note: This is ignored in most WebGL implementations (especially in Chrome), which only support 1.
linecap	String	'round'	Defines the shape at the ends of the lines. Options: 'butt', 'round', 'square'. Mostly used in 2D canvas rendering.
linejoin	String	'round'	Shape used at corners where two lines join. Options: 'round', 'bevel', 'miter'.
vertexColors	Boolean	false	If set to true, the color will be taken from each vertex (geometry.attributes.color).
fog	Boolean	true	Whether the material is affected by fog in the scene.
transparent	Boolean	false	Whether to enable transparency. Requires opacity < 1 or transparent textures.
opacity	Number	1.0	Opacity level; 0 is fully transparent, 1 is fully opaque.

Parameter	Type	Default	Description
<code>depthTest</code>	Boolean	<code>true</code>	Whether to check depth before drawing (default true for proper occlusion).
<code>depthWrite</code>	Boolean	<code>true</code>	Whether writing to the depth buffer is enabled.
<code>blending</code>	Number	<code>THREE.NormalBlending</code>	Blending mode (additive, subtractive, etc.) for transparency.
<code>side</code>	Number	<code>THREE.FrontSide</code>	Not often used in lines, but defines whether front, back, or both sides are rendered.

🚫 Browser Limitations (Important!)

- `linewidth` is only supported in **Firefox** and some native contexts.
- On **most platforms (e.g., Chrome/WebGL)** , line width will always be `1`.

✅ When to Use

Use `LineBasicMaterial` when:

- You want simple lines (e.g., wireframes, helpers, guides).
- You don't need lighting effects.
- You care about performance and simplicity.

THREE.LineDashedMaterial()

This material renders dashed or dotted lines using a pattern of **dashes and gaps** , and is useful for outlines, grids, or helper visuals.

SYNTAX--

```
const dashedMaterial = new THREE.LineDashedMaterial({
  color: 0xff0000,
  linewidth: 1,
  scale: 1,
  dashSize: 3,
  gapSize: 1,
});
```

Parameters same like that of `LineBasicMaterial()`. Other than it has theses--

scale **Number** **1** **Global scale factor for dash and gap sizes.**

dashSize **Number** **3** **Length of each dash.**

gapSize **Number** **1** **Length of each gap between dashes.**

Important Usage Note

To make `LineDashedMaterial` work properly, you **must call** `geometry.computeLineDistances()` before rendering.

EXAMPLE--

```
const points = [  
  new THREE.Vector3(0, 0, 0),  
  new THREE.Vector3(5, 0, 0),  
];  
const geometry = new THREE.BufferGeometry().setFromPoints(points);  
geometry.computeLineDistances(); // REQUIRED for dashes  
  
const dashedMaterial = new THREE.LineDashedMaterial({  
  color: 0x0000ff,  
  dashSize: 0.5,  
  gapSize: 0.2,  
  scale: 1,  
});  
  
const line = new THREE.Line(geometry, dashedMaterial);  
scene.add(line);
```

How Dash Works Visually

If you think of a line as:

- Each **dashSize** is a solid part.
- Each **gapSize** is the empty space in between.
- **scale** multiplies both.

THREE.Vector3()

`THREE.Vector3()` is a fundamental class in Three.js used to represent **points or directions in 3D space** using **x, y, z** coordinates.

SYNTAX--- `const vector = new THREE.Vector3(x, y, z);`

- **x**: The x-coordinate (default is 0)
- **y**: The y-coordinate (default is 0)
- **z**: The z-coordinate (default is 0)

Example:

```
const v1 = new THREE.Vector3(1, 2, 3);
const v2 = new THREE.Vector3(4, 5, 6);

// Add vectors
v1.add(v2); // v1 is now (5, 7, 9)
```

Common Methods

Method	Description
<code>.add(v)</code>	Adds another Vector3 to this one.
<code>.sub(v)</code>	Subtracts another Vector3 from this one.
<code>.multiplyScalar(s)</code>	Multiplies all components by a scalar s .
<code>.length()</code>	Returns the Euclidean length.
<code>.normalize()</code>	Normalizes the vector (length becomes 1).
<code>.dot(v)</code>	Dot product with another vector.
<code>.cross(v)</code>	Cross product with another vector.
<code>.distanceTo(v)</code>	Euclidean distance to another vector.
<code>.clone()</code>	Creates a new Vector3 instance with the same values. Use when you want a completely separate copy.
<code>.copy()</code>	Copies values from another vector into the existing one. Use when you already have an object and want to overwrite it.

Method	Description
<code>.set(x, y, z)</code>	Sets all three components.



Usage Examples

Setting a position: `mesh.position = new THREE.Vector3(10, 0, -5);`

Direction vector: `const direction = new THREE.Vector3(1, 0, 0).normalize();`

Apply transformation: `v1.applyMatrix4(matrix);` // Applies a transformation matrix

Perspective Camera and Field Of View (FOV) (Refer Note)

Field of View (FOV) refers to how much of the scene a camera can see at once. It's like the **angle of vision** for the camera — wider angles mean you see more, narrower angles mean you zoom in more.

In 3D Graphics (like Three.js):

When using a **Perspective Camera**, FOV is usually the **vertical angle** (in degrees) that defines the viewing area. For example:

```
const camera = new THREE.PerspectiveCamera(fov, aspect, near, far);
```

- **fov** : Field of view in degrees (vertical angle). 35 and 50 are the most common values.
- **aspect** : Width / height ratio of the view.
- **near & far** : How close and how far the camera can see.



Think of it like this:

- **Low FOV (e.g., 30°)** → Zoomed in (like a sniper scope).
- **High FOV (e.g., 90°–120°)** → Wide-angle view (like a GoPro).



Real-World Analogy:

- Your human eyes have an FOV of around **120–180° horizontally**.
- A phone camera typically has an FOV of **60–80°**.

FOV Range Of Values

- **Typical Range** : 1° to 179°
- **Too small (e.g. $1-10^\circ$)** → Very **zoomed-in** , like a telescope.
- **Typical ($45-75^\circ$)** → Natural camera look.
- **Wide ($90-120^\circ$)** → Wide-angle lens. Fish-eye at the extreme end.
- **Near 180°** → Unrealistic or distorted.

🔴 Values above 179° are not practical because the scene becomes visually unstable and mathematically problematic.

□ **near** – Near Clipping Plane

✅ What is it?

- The **closest distance** from the camera at which objects are **visible** .
- Anything **closer** than this will be **clipped** (invisible).

✏️ **Range of Values:**

- Must be **greater than 0** (never 0).
- Typical range: 0.1 to 1.0 units.
- In Three.js and similar engines, units are arbitrary (could be meters, feet, etc.)

📌 A smaller **near** value allows you to see objects closer to the camera, but too small a value can cause **depth buffer precision problems** (more on that below).

🔵 **far** – Far Clipping Plane

✅ What is it?

- The **farthest distance** the camera can see.
- Anything beyond this will be **clipped** (not rendered).

✏️ **Range of Values:**

- Any value **greater than near** .
- Typical range: 100 , 1000 , even 10000 , depending on scene size.

📌 The larger the **far** value, the more area the camera can see — but it can cause **depth precision issues** .

⚠️ **Clipping Planes and Depth Precision**

The space between **near** and **far** is where the **depth buffer** operates. The **depth buffer** helps determine which objects are in front of others.

- If the range between **near** and **far** is **too large** (e.g., **near** = 0.1, **far** = 10000), it can cause **z-fighting** (objects flickering or rendering incorrectly).
- A **balanced ratio** (like **near** = 0.1, **far** = 1000) is ideal.

Usual Values---- `const camera = new THREE.PerspectiveCamera(35, window.innerWidth/window.innerHeight, 0.1, 200);`

 Summary Table

Parameter	Meaning	Typical Range	Too Low/High Risk
fov	Vertical field of view (degrees)	30–90°	Distortion or fish-eye effects
near	Closest visible distance	0.1–1.0	Precision issues if too small
far	Farthest visible distance	100–10000	Z-fighting if too large compared to near

 Important Properties

Property	Description
fov	Field of view (vertical, in degrees)
aspect	Aspect ratio (width / height)
near	Near clipping plane distance
far	Far clipping plane distance
zoom	Zoom level (default is 1)
focus	Focal length for depth of field (used in some post-processing)
view	Used for multi-camera or tiled rendering
filmGauge	Used for depth-of-field calculations
filmOffset	Horizontal offset in the film plane
position	Camera’s position (Vector3)
rotation	Euler rotation (pitch, yaw, roll)

Property	Description
<code>quaternion</code>	Camera rotation in quaternion form
<code>up</code>	The up direction (default is (0, 1, 0))
<code>projectionMatrix</code>	The 4x4 projection matrix (auto-generated)
<code>matrixWorld</code>	The world transformation matrix of the camera

The `view` property of a `PerspectiveCamera` or `OrthographicCamera` is used to define a **subset of the rendering area**, enabling techniques like:

- **Multi-view rendering**
- **Split-screen**
- **Tiled rendering**
- **Virtual reality (VR) stereo cameras**

 What is `camera.view`?

The `view` property holds an **object** that defines a custom viewport (a subsection of the full camera frustum). When it's set, the camera will only render a portion of its full frustum.

Structure of `camera.view`

```
camera.view = {
  enabled: true,           // must be true to activate the view offset
  fullWidth: number,      // full width of the virtual screen
  fullHeight: number,     // full height of the virtual screen
  offsetX: number,        // x offset of the sub-camera
  offsetY: number,        // y offset of the sub-camera
  width: number,          // width of the sub-camera
  height: number          // height of the sub-camera
}
```

Why Use It?

You typically don't set `view` manually — instead, you use the camera method:

```
camera.setViewOffset(fullWidth, fullHeight, offsetX, offsetY, width, height);
```

Which internally updates the `camera.view` property and changes the **projection matrix** accordingly.

Example – Split-Screen View (Left/Right)

Suppose you want to render two views side-by-side (e.g., for VR or multiplayer):

```
// Full virtual screen size
const fullWidth = window.innerWidth;
const fullHeight = window.innerHeight;

// Left view
leftCamera.setViewOffset(fullWidth, fullHeight, 0, 0, fullWidth / 2,
fullHeight);

// Right view
rightCamera.setViewOffset(fullWidth, fullHeight, fullWidth / 2, 0, fullWidth /
2, fullHeight);
```

Each camera now renders just **half** of the scene's view, but from its own perspective.

Reset View Offset---- `camera.clearViewOffset();`

This disables the view offset and reverts the camera to its normal full frustum rendering.

Methods

Method	Description
<code>updateProjectionMatrix()</code>	Recalculates the projection matrix when any of <code>fov</code> , <code>aspect</code> , <code>near</code> , or <code>far</code> change
<code>lookAt(x, y, z)</code>	Makes the camera point at a given position
<code>setFocalLength(focalLength)</code>	Sets the field of view based on a focal length in mm
<code>getFocalLength()</code>	Returns the focal length corresponding to the current FOV
<code>setViewOffset(width, height, x, y, width2, height2)</code>	Used for multi-window or multi-monitor rendering

Method	Description
<code>clearViewOffset()</code>	Clears any view offset applied
<code>updateMatrixWorld(force)</code>	Updates the <code>matrixWorld</code> recursively
<code>getWorldDirection(target)</code>	Returns the camera's viewing direction as a unit vector

Common Lifecycle Usage

```
camera.fov = 60;  
camera.aspect = window.innerWidth / window.innerHeight;  
camera.updateProjectionMatrix(); // Must call this after changes
```

Example Usage

```
const camera = new THREE.PerspectiveCamera(75, window.innerWidth/window.innerHeight,  
0.1, 1000);  
camera.position.set(0, 2, 5);  
camera.lookAt(0, 0, 0);
```

Camera Position

By Default:

When you create a camera like this:

```
const camera = new THREE.PerspectiveCamera(fov, aspect, near, far);  
camera.position.set(0, 0, 10);
```

It will **look down the negative Z-axis** by default — **not necessarily at the origin** .

So in the above case, it's looking toward `(0, 0, 0)` only **if** the object lies in that direction from its position on the positive Z-axis.

To make the camera face the origin:

You **must explicitly tell it** to look at the origin:

```
camera.lookAt(0, 0, 0);
```

Or with a vector:

```
camera.lookAt(new THREE.Vector3(0, 0, 0));
```

Real-Life Analogy

Just because you're standing somewhere in a room doesn't mean you're **looking at the center**. You could be looking at the wall, ceiling, or door unless you intentionally face the center.

Shape

Shape is a **class in Three.js** that represents a **2D shape** defined by lines and curves. It is commonly used to create **custom 2D outlines** which can later be:

- Extruded into 3D with **ExtrudeGeometry**
- Converted into flat geometry with **ShapeGeometry**

Basic Purpose:

To **define 2D paths** (like circles, stars, or custom shapes) that can be rendered or turned into 3D.

 **Syntax:** `const shape = new THREE.Shape();`

You then **use methods like** `.moveTo()` and `.lineTo()` to define the outline.

Example — Creating a Square Shape:

```
const shape = new THREE.Shape();
shape.moveTo(0, 0);           // Starting point
shape.lineTo(0, 100);         // Line up
shape.lineTo(100, 100);       // Line right
shape.lineTo(100, 0);         // Line down
shape.lineTo(0, 0);           // Close the shape
```

This defines a **square** from $(0,0)$ to $(100,100)$.

Common Shape Methods:

- `.moveTo(x, y)` → Moves the drawing cursor.
- `.lineTo(x, y)` → Draws a straight line.
- `.bezierCurveTo(...)` / `.quadraticCurveTo(...)` → Draws curves.
- `.absarc(...)` → Draws an arc or circle.

Turning Shape into Renderable Geometry:

```
const geometry = new THREE.ShapeGeometry(shape);
const material = new THREE.MeshBasicMaterial({ color: 0x00ff00 });
const mesh = new THREE.Mesh(geometry, material);
scene.add(mesh);
```

This renders the 2D shape as a **flat green mesh** in your scene.

Use Cases:

- Custom buttons or icons
- 3D text backgrounds
- Extruded logos or designs
- 2D cutouts for 3D printing

Line

In **Three.js**, `THREE.Line` is used to draw **straight or curved lines** in 3D space, using a **geometry** and a **material**.

Purpose:

To **render lines** (not surfaces) between points in 3D space — useful for:

- Wireframes
- Graphs and grids
- Trajectories
- Visual helpers like axes

Syntax:

```
const line = new THREE.Line(geometry, material);
```

- `geometry`: A `THREE.BufferGeometry` that contains the line's points.
- `material`: A `THREE.LineBasicMaterial` or `THREE.LineDashedMaterial`.

Example — Drawing a Simple Line Between Two Points:

```
const points = [  
  new THREE.Vector3(0, 0, 0),  
  new THREE.Vector3(1, 1, 0)  
];  
  
const geometry = new THREE.BufferGeometry().setFromPoints(points);  
  
const material = new THREE.LineBasicMaterial({ color: 0xff0000 });  
  
const line = new THREE.Line(geometry, material);  
scene.add(line);
```

✅ This creates a red line from (0, 0, 0) to (1, 1, 0).

Related Types:

- `THREE.LineSegments` → For multiple disconnected lines.
- `THREE.LineLoop` → Like `THREE.Line`, but automatically **connects last point to first**, forming a loop.

Materials:

- `THREE.LineBasicMaterial` → Simple colored line.
- `THREE.LineDashedMaterial` → Dashed lines (requires `computeLineDistances()` on geometry).

Use Cases:

- Drawing outlines and edges
- Creating 3D coordinate axes
- Making dynamic paths (e.g., for animation or movement trails)
- Debugging geometries

OrbitControls

`THREE.OrbitControls` is a **helper class** in Three.js that allows the **camera to orbit around a target** using mouse or touch input — just like you'd expect in a 3D editor or 3D viewer.

What Does `OrbitControls` Do?

It enables **interactive control** over the camera:

- Rotate/orbit the camera around a target
- Zoom in/out
- Pan the view
- Damping (smooth transition)
- Restrict angles/distance

How to Use It

1. Import OrbitControls

If you're using modules:

```
import { OrbitControls } from  
'three/examples/jsm/controls/OrbitControls.js';
```

2. Create the Controls

```
const controls = new OrbitControls(camera, renderer.domElement);
```

- `camera`: The camera you want to control.
- `renderer.domElement`: The HTML canvas element to listen for events (usually `renderer.domElement`).

Main Properties

Rotation (Orbiting)

- `controls.target`: A `THREE.Vector3` where the camera orbits around.
- By default: `(0, 0, 0)`
- You can change it:

```
controls.target.set(1, 2, 3);
controls.update(); // Required after changing target
```

Zooming

- **Mouse wheel** or two-finger pinch.
- Controlled by:
 - `controls.enableZoom` → `true` by default
 - `controls.minDistance` & `controls.maxDistance`

Panning (Right-click or two-finger drag)

- Moves the camera and target **together**
- Controlled by:
 - `controls.enablePan` → `true` by default
 - `controls.screenSpacePanning`:
 - `true`: pan parallel to screen (default)
 - `false`: pan along camera's up direction

Damping (Smooth Movement)

- Makes the camera ease into motion

```
controls.enableDamping = true;
controls.dampingFactor = 0.05;
```

- You **must call** `controls.update()` on every frame for damping to work.

Limit Rotation

- `controls.minPolarAngle` & `controls.maxPolarAngle`:
 - Restricts vertical orbiting (0 = top, `Math.PI` = bottom).
 - Example: Prevent camera from going below the object:
`controls.maxPolarAngle = Math.PI / 2;`
- `controls.minAzimuthAngle` & `controls.maxAzimuthAngle`:
 - Restricts horizontal orbiting (like left-right camera rotation).

Limit Zoom

```
controls.minDistance = 5;  
controls.maxDistance = 50;
```

Disabling Controls Dynamically ---- `controls.enabled = false;`

Events

- `controls.addEventListener('change', callback):`
 - Useful when you want to render only on interaction (e.g., no animation loop).

Mobile Support

Works with touch events:

- One finger drag = rotate
- Two fingers = zoom/pan

Typical Example Setup

```
import * as THREE from 'three';  
import { OrbitControls } from 'three/examples/jsm/controls/OrbitControls';  
  
const scene = new THREE.Scene();  
const camera = new THREE.PerspectiveCamera(75, window.innerWidth/window.innerHeight,  
0.1, 1000);  
camera.position.set(0, 2, 5);  
  
const renderer = new THREE.WebGLRenderer();  
renderer.setSize(window.innerWidth, window.innerHeight);  
document.body.appendChild(renderer.domElement);  
  
const controls = new OrbitControls(camera, renderer.domElement);  
controls.enableDamping = true;  
controls.dampingFactor = 0.1;  
  
function animate() {  
    requestAnimationFrame(animate);  
    controls.update(); // Required if damping is enabled  
    renderer.render(scene, camera);  
}  
animate();
```

Summary Table

Feature	Property	Default
Enable Zoom	<code>enableZoom</code>	<code>true</code>
Enable Pan	<code>enablePan</code>	<code>true</code>
Enable Rotate	<code>enableRotate</code>	<code>true</code>
Enable Damping	<code>enableDamping</code>	<code>false</code>
Damping Speed	<code>dampingFactor</code>	<code>0.05</code>
Zoom Limits	<code>minDistance,maxDistance</code>	<code>0, ∞</code>
Rotation Limits	<code>minPolarAngle,maxPolarAngle</code>	<code>0, π</code>
Pan Speed	<code>panSpeed</code>	<code>1.0</code>

What is `renderer.domElement`?

This creates a WebGL-based renderer. Internally, it creates an HTML `<canvas>` element to render 3D content.

```
const renderer = new THREE.WebGLRenderer();
```

Now, `renderer.domElement` is a **reference to the actual `<canvas>` HTML element created by `WebGLRenderer`**

You can then use it like this to **insert the canvas into your webpage** , so users can see the 3D scene.:

```
document.body.appendChild(renderer.domElement);
```

Also, when you do:

```
new OrbitControls(camera, renderer.domElement);
```

You're telling the controls to listen for **mouse and touch events** on that canvas. This allows users to rotate, zoom, or pan the camera **only when interacting with the 3D canvas** , not the rest of the page.

Now in order to use a specific `<canvas>` element from your HTML instead of letting Three.js create one for you.

```
const canvas = document.querySelector("canvas.threejs");
const renderer = new THREE.WebGLRenderer({
  canvas: canvas,
});
```

you're telling Three.js:

👉 "Use this canvas that I already have in the HTML to render the 3D scene."

This gives you more control over your HTML layout and avoids having to call: `document.body.appendChild(renderer.domElement);` because the canvas is already in the DOM.

📋 PROPERTIES

Property	Type	Description
<code>enabled</code>	Boolean	Enable/disable all user interactions. Default: <code>true</code> .
<code>target</code>	<code>THREE.Vector3</code>	The point the camera orbits around. Default: <code>(0, 0, 0)</code> .
<code>minDistance</code>	Number	Minimum distance for dolly/zoom.
<code>maxDistance</code>	Number	Maximum distance for dolly/zoom.
<code>minZoom</code>	Number	Minimum zoom (only for <code>OrthographicCamera</code>).
<code>maxZoom</code>	Number	Maximum zoom (only for <code>OrthographicCamera</code>).
<code>minPolarAngle</code>	Number	Limits vertical rotation (in radians). Default: <code>0</code> .
<code>maxPolarAngle</code>	Number	Limits vertical rotation. Max: <code>Math.PI</code> .
<code>minAzimuthAngle</code>	Number	Limits horizontal rotation. Default: <code>-Infinity</code> .

Property	Type	Description
<code>maxAzimuthAngle</code>	Number	Limits horizontal rotation. Default: <code>Infinity</code> .
<code>enableDamping</code>	Boolean	Enables inertial movement (smooth). Must call <code>controls.update()</code> in the animation loop. Default: <code>false</code> .
<code>dampingFactor</code>	Number	Damping inertia strength. Default: <code>0.05</code> .
<code>enableZoom</code>	Boolean	Enable/disable zooming. Default: <code>true</code> .
<code>zoomSpeed</code>	Number	Speed of zooming. Default: <code>1.0</code> .
<code>enableRotate</code>	Boolean	Enable/disable rotation. Default: <code>true</code> .
<code>rotateSpeed</code>	Number	Speed of rotation. Default: <code>1.0</code> .
<code>enablePan</code>	Boolean	Enable/disable panning. Default: <code>true</code> .
<code>panSpeed</code>	Number	Speed of panning. Default: <code>1.0</code> .
<code>screenSpacePanning</code>	Boolean	If <code>true</code> , pan in screen-space. If <code>false</code> , pan in world-space. Default: <code>true</code> .
<code>keyPanSpeed</code>	Number	Speed of panning using keyboard. Default: <code>7.0</code> .
<code>autoRotate</code>	Boolean	Automatically rotate around the target. Default: <code>false</code> .
<code>autoRotateSpeed</code>	Number	Speed of automatic rotation. Default: <code>2.0</code> .
<code>enableKeys</code>	Boolean	Enable keyboard controls. Default: <code>true</code> .
<code>keys</code>	Object	Key mapping for keyboard interaction. Default: <code>{ LEFT: 37, UP: 38, RIGHT: 39, BOTTOM: 40 }</code> .
<code>mouseButtons</code>	Object	Assign actions to mouse buttons. Default:

What is `screenSpacePanning` in `OrbitControls`?

`screenSpacePanning` is a boolean property in `OrbitControls` that changes **how the camera pans** :

- `screenSpacePanning: true` → Panning moves the camera **in the screen's 2D X-Y direction** (like dragging a piece of paper).

- `screenSpacePanning: false` → Panning moves **along the camera's local up/right axes** (more like orbiting/pushing in 3D space).

Real-World Analogy

1. Screen-space panning (`screenSpacePanning: true`)

Like dragging a photo around with your finger on a touchscreen.

- The image moves **left/right or up/down** exactly as your finger moves, no matter how the camera is tilted.
- Movement is tied to **the 2D screen plane**, not the 3D world.

🟢 Best when you want predictable flat movement – e.g. **2D maps**, **UI overlays**, **CAD tools**.

2. World-space panning (`screenSpacePanning: false`)

Like moving your head while looking at a model – if you're tilted, "up" might move you sideways.

- Movement happens along the **camera's up and right directions** in 3D space.
- It respects the **camera's rotation**, so dragging "up" might push the camera in a diagonal path if the view is tilted.

🟢 Best when you want movement to feel **natural in 3D space** – e.g. **3D scenes**, **architectural walkthroughs**.

✅ **Can we use an Orthographic Camera instead of `screenSpacePanning: true`?**

Yes — often!

If your goal is **flat, screen-aligned movement** (like 2D maps or CAD interfaces), an **orthographic camera** is usually a *better fit* than forcing a perspective camera to behave similarly using `screenSpacePanning`.

🧠 Why?

 **PerspectiveCamera + `screenSpacePanning: true`**

- Still uses **perspective projection**, meaning:

- Things closer to the camera look bigger.
- Panning mimics 2D movement but in a 3D projection space.
- You're kind of *fighting* the perspective camera to make it feel 2D.

■ OrthographicCamera

- Uses **orthographic projection** :
 - No perspective distortion.
 - All objects are the same size regardless of depth.
 - Movement is inherently **2D-like** and linear.
- This is the natural camera for:
 - Maps
 - 2D games
 - Architectural plans
 - CAD tools
 - UI overlays in 3D environments

🔧 METHODS (with description)

Method	Description
<code>update()</code>	Updates the camera position based on user interaction, damping, or auto-rotation. Must be called each frame if <code>enableDamping</code> or <code>autoRotate</code> is enabled.
<code>reset()</code>	Resets the camera position, target, and zoom to the initial state (when <code>OrbitControls</code> was created or last time <code>saveState()</code> was called).
<code>dispose()</code>	Removes all event listeners from the controls. Call this method when you're cleaning up the scene (e.g., navigating to another page or destroying the canvas).
<code>saveState()</code>	Saves the current camera and target state so you can later call <code>reset()</code> or <code>restoreState()</code> to return to this exact view.

Method	Description
<code>restoreState()</code>	Restores the camera and target to the last state saved using <code>saveState()</code> .
<code>getPolarAngle()</code>	Returns the camera's polar angle (vertical angle) in radians. Useful to understand how far up/down the camera is rotated.
<code>getAzimuthalAngle()</code>	Returns the camera's azimuthal angle (horizontal angle) in radians. Useful to track how far around the target the camera has moved.
<code>listenToKeyEvents(domElement)</code>	Starts listening for keyboard input on a specific DOM element. Useful when you want keyboard control to only apply to a certain part of the UI.

Render Loop

In **Three.js**, the **render loop** (often called the **animation loop**) is the heart of your 3D application. It is what keeps your scene alive — continuously updating the screen by rendering changes in camera, controls, animations, physics, or user interactions.



What is a Render Loop?

A **loop that runs continuously**, usually using `requestAnimationFrame()`, to:

- Update object positions (animations, controls)
- Update physics (if using)
- Re-render the scene from the camera's perspective



Basic Structure of a Render Loop

```
function animate() {
  requestAnimationFrame(animate); // Schedule the next frame
  controls.update();               // If controls like OrbitControls have damping
  renderer.render(scene, camera); // Draw the scene
}
```

```
animate(); // Start the loop
```



Why Use `requestAnimationFrame()`?

`requestAnimationFrame()` is the browser's built-in function for smooth animation:

- Runs at **native refresh rate** (usually 60 FPS)
- Pauses when the tab is inactive → saves performance
- Syncs with the browser's repaint → smooth animations

❌ **DO NOT** use `setInterval()` or `setTimeout()` or any selfcalling loops— they are less efficient and less smooth.



Breakdown of What Happens in the Loop

Each frame, you might do things like:

```
function animate() {
  requestAnimationFrame(animate);

  // 1. Update animations
  mixer.update(deltaTime);           // If using AnimationMixer

  // 2. Update controls
  controls.update();                 // For OrbitControls with damping

  // 3. Custom logic
  cube.rotation.y += 0.01;          // Example: spin an object

  // 4. Physics simulation
  // physicsEngine.step();           // Optional

  // 5. Render the updated scene
  renderer.render(scene, camera);
}
```



Time-Based Animation (Delta Time)

To make animations consistent regardless of FPS:

```

const clock = new THREE.Clock();

function animate() {
  requestAnimationFrame(animate);

  const delta = clock.getDelta(); // Time since last frame (in seconds)

  cube.rotation.y += 1 * delta; // Rotate 1 radian/sec regardless of FPS
  renderer.render(scene, camera);
}

```

✿ Integration with OrbitControls

If you're using **OrbitControls** with damping , you must call **controls.update()** every frame in the loop:

```

controls.enableDamping = true;
controls.dampingFactor = 0.05;

function animate() {
  requestAnimationFrame(animate);
  controls.update(); // Required for smooth damping
  renderer.render(scene, camera);
}

```

✍ Full Example

```

import * as THREE from 'three';
import { OrbitControls } from 'three/examples/jsm/controls/OrbitControls';

const scene = new THREE.Scene();
const camera = new THREE.PerspectiveCamera(75, window.innerWidth/window.innerHeight, 0.1, 1000);
camera.position.set(0, 1, 5);

const renderer = new THREE.WebGLRenderer({ antialias: true });
renderer.setSize(window.innerWidth, window.innerHeight);
document.body.appendChild(renderer.domElement);

// Add a spinning cube
const geometry = new THREE.BoxGeometry();
const material = new THREE.MeshNormalMaterial();
const cube = new THREE.Mesh(geometry, material);
scene.add(cube);

// Controls

```

```

const controls = new OrbitControls(camera, renderer.domElement);
controls.enableDamping = true;
controls.dampingFactor = 0.1;

// Clock for delta time
const clock = new THREE.Clock();

// Render loop
function animate() {
    requestAnimationFrame(animate);

    const delta = clock.getDelta();
    cube.rotation.y += delta;

    controls.update();          // For damping
    renderer.render(scene, camera);
}

animate();

```

📌 `const clock = new THREE.Clock();`

This creates a **clock** that keeps track of time in your animation. Think of it as an internal stopwatch that measures how much time has passed between frames.

It's mainly used to handle animations smoothly and consistently, regardless of the frame rate.

📌 `const delta = clock.getDelta();`

- This returns the **time in seconds** that has passed **since the last time `getDelta()` was called** . For example, if the frame rate is 60 FPS, `delta` would be approximately $1/60 \approx 0.016$ seconds.
- If your frame rate drops, `delta` increases (e.g., 0.03 at 30 FPS).

❓ Why use `clock.getDelta()` instead of a fixed value?

Using `delta` makes your animations **frame rate-independent** .

You're doing: `cube.rotation.y += delta;`

This means:

- If the frame rate is fast, the cube rotates in **small steps** .
- If the frame rate slows down, the cube rotates in **larger steps** .

✅ So regardless of how fast or slow the device is, the cube spins at the **same speed over time** , not per frame.

Renderer.SetPixelRatio

To set a pixel ratio. Sometimes you don't want to use the max pixel ratio to avoid cpu usage. Hence,

```
renderer.setPixelRatio(Math.min(window.devicePixelRatio, 2))
```

It also works as an Antialiasing strategy(Not for every device) because by default value would be less than 1 or 1. So by above code if at all the pixel ratio is 2 or more one can use the above code

Clock

THREE.Clock is a **built-in utility class in Three.js** designed to **track time** between frames. It's extremely useful for creating **time-based animations** , physics simulations, or managing any logic that depends on elapsed time.

📦 Why not just use `Date.now()` or `performance.now()`?

You *could* — but **THREE.Clock** wraps that functionality in a **cleaner** , more **consistent** API and makes tracking **frame-to-frame deltas** or **total elapsed time** very easy.

🧠 Basic Usage

```
const clock = new THREE.Clock();
```

This creates a new clock and starts it immediately.

Some Methods

1. **🔄 `clock.getDelta()` **

```
const delta = clock.getDelta();
```

- Returns the **time in seconds** since the last call to `getDelta()`.
- Also **updates the internal clock time** to "now".
- Usually used inside your `animate()` or `render()` loop.
- Commonly used for **frame-rate independent animations**.

Example: `cube.rotation.x += delta; // consistent rotation speed even if frame rate drops`

2. `clock.getElapsedTime()`

```
const elapsed = clock.getElapsedTime();
```

- Returns the **total time (in seconds)** since the clock was started or last reset.
- Does **not update** any internal state.
- Useful for things like:
 - Waving effects: `Math.sin(clock.getElapsedTime())`
 - Showing a timer
 - Looping animations

3. `clock.stop()` and `clock.start()`

- `clock.stop()` → stops the clock (freezes time)
- `clock.start()` → resumes the clock from where it was paused
- Note: `getDelta()` will return 0 after stopping, until the clock is restarted.

4. `clock.running`

- A boolean that tells you whether the clock is currently running.

Use Case Example (delta-based rotation)

```
const clock = new THREE.Clock();

function animate() {
  requestAnimationFrame(animate);

  const delta = clock.getDelta();
  cube.rotation.y += delta * 2; // rotate 2 radians per second

  renderer.render(scene, camera);
}
```

Even if FPS drops from 60 → 30, this ensures the cube **still rotates at a consistent speed**, because `delta` adjusts for the delay between frames.

Common Mistake to Avoid

Calling `getDelta()` **more than once per frame** (in different parts of your code) will give **different values** and cause inconsistencies.

So:

 Call it once per frame, store it in a variable, and reuse that variable.

Orthographic Camera

An **Orthographic Camera** is a type of camera in 3D graphics that renders **objects without perspective distortion**. That means:

- Objects **don't get smaller** as they move farther from the camera.
- Parallel lines stay parallel (they don't converge at vanishing points).

Real-World Analogy

- **Perspective Camera** (like `THREE.PerspectiveCamera`) is how **humans see**: things far away look smaller.
- **Orthographic Camera** is like looking at a **blueprint** or **technical drawing**: everything stays the same size, no matter how far away it is.

Use Cases

- **2D games** and **UIs** inside 3D environments
- **CAD software** (Computer-Aided Design)
- **Architectural visualization**
- **Strategy games** and **map views**
- **Pixel-perfect rendering**, like sprite-based scenes

Syntax in Three.js

```
const camera = new THREE.OrthographicCamera(  
  left,    // min x  
  right,   // max x  
  top,     // max y
```

```
bottom, // min y
near,   // near clipping plane
far     // far clipping plane
);
```

Example:

```
const aspect = window.innerWidth / window.innerHeight;
const frustumSize = 10;

const camera = new THREE.OrthographicCamera(
  -frustumSize * aspect / 2, // left
  frustumSize * aspect / 2,  // right
  frustumSize / 2,           // top
  -frustumSize / 2,          // bottom
  0.1,                        // near
  1000                        // far
);
camera.position.set(0, 0, 10);
camera.lookAt(0, 0, 0);
```

What's going on here?

- **frustumSize**: Controls how large your view is.
- You calculate the camera's bounds based on the aspect ratio and size to keep the scaling consistent.

camera.position.set(0, 0, 10);

This sets the **position of the camera** in 3D space.

- **0**: X-axis → center horizontally
- **0**: Y-axis → center vertically
- **10**: Z-axis → 10 units in front of the origin

So, the camera is placed **10 units in front of the center point (0, 0, 0)** of your scene — looking straight toward it from the Z-axis.

Think of it like this:

- The camera is standing at point **(0, 0, 10)** and **facing inward toward the screen**, down the -Z direction.

camera.lookAt(0, 0, 0);

This tells the camera to **look at a specific point** in 3D space.

- Here, it's set to look at the origin $(0, 0, 0)$ — the center of the scene.
- This means whatever object is placed at $(0, 0, 0)$ will be directly in the center of the camera's view.

So: even though the camera is *positioned* at $(0, 0, 10)$, this makes sure it is *facing* $(0, 0, 0)$.

✅ Advantages

- Straight lines stay straight.
- No distortion — great for technical or stylized views.
- Useful when **consistent scale** matters (e.g. 2D grid, overlays).

⚠️ Limitations

- No sense of depth through size (you can't tell how far something is just by looking).
- Not natural for human vision (can look flat or unrealistic if used improperly).

🔄 Switching Cameras

You can switch between an orthographic and perspective camera in the same scene if needed (e.g., for minimaps or toggling views).

```
let isOrtho = true;

function toggleCamera() {
  if (isOrtho) {
    camera = new THREE.PerspectiveCamera(...);
  } else {
    camera = new THREE.OrthographicCamera(...);
  }
  isOrtho = !isOrtho;
}
```

📦 Properties

Property	Description
<code>left</code>	Left boundary of the view frustum
<code>right</code>	Right boundary of the view frustum

Property	Description
<code>top</code>	Top boundary of the view frustum
<code>bottom</code>	Bottom boundary of the view frustum
<code>near</code>	Near clipping plane
<code>far</code>	Far clipping plane
<code>zoom</code>	Zoom factor (default is <code>1</code>)
<code>view</code>	Object for view offset (used in tiled rendering, split view, VR)
<code>position</code>	Camera's position in 3D space (<code>THREE.Vector3</code>)
<code>rotation</code>	Rotation in Euler angles
<code>quaternion</code>	Rotation as a quaternion
<code>up</code>	"Up" direction (default is <code>(0, 1, 0)</code>)
<code>projectionMatrix</code>	The camera's projection matrix
<code>matrixWorld</code>	The camera's global transformation matrix

Methods

Method	Description
<code>updateProjectionMatrix()</code>	Recalculates the projection matrix (must be called after changing <code>left</code> , <code>right</code> , etc.)
<code>lookAt(vector)</code>	Makes the camera point at a given position (e.g., <code>camera.lookAt(0, 0, 0)</code>)
<code>setViewOffset(fullWidth, fullHeight, x, y, width, height)</code>	Enables and configures view offset
<code>clearViewOffset()</code>	Disables view offset
<code>updateMatrixWorld(force)</code>	Updates the camera's world transformation matrix
<code>getWorldDirection(target)</code>	Returns a unit vector in the camera's forward direction

Method	Description
<code>clone()</code>	Clones the camera and returns a new instance
<code>copy(camera)</code>	Copies the properties from another camera instance

Typical Usage

```
const aspect = window.innerWidth / window.innerHeight;
const camera = new THREE.OrthographicCamera(
  -aspect * 5, // left
  aspect * 5, // right
  5,          // top
  -5,         // bottom
  0.1,        // near
  1000        // far
);
camera.position.set(0, 0, 10);
camera.lookAt(0, 0, 0);
```

 Always call `camera.updateProjectionMatrix()` after changing properties like `left`, `right`, `top`, `bottom`, or `zoom`.

Summary Table

Feature	Orthographic Camera	Perspective Camera
View style	Flat, blueprint-style	Realistic, human-like
Distant object size	Same as close objects	Smaller as they get farther
Use cases	UI, 2D games, CAD, technical visuals	Most 3D games and scenes
Depth perception	No size-based cues	Natural size-based depth cues

Controls

In **Three.js**, *controls* allow you to interactively navigate a scene using mouse, keyboard, or touch input. The most commonly used control types are part of the

`three/examples/jsm/controls` module.

Here's a list of the most popular **control types** and what they're used for



Commonly Used Three.js Controls

1. OrbitControls
2. TrackballControls
3. ArcballControls
4. PointerLockControls
5. MapControls
6. FirstPersonControls
7. FlyControls

1. OrbitControls

- **Purpose** : Orbit around a target.
- **Usage** : Best for general scene navigation (e.g., rotating, zooming, panning).
- **Features** :
 - Mouse/touch orbiting
 - Zoom in/out
 - Pan left/right/up/down
 - Damping (inertia-like effect)
- **Example** :

```
import { OrbitControls } from 'three/examples/jsm/controls/OrbitControls';  
const controls = new OrbitControls(camera, renderer.domElement);
```

2. TrackballControls

We can move in 4 directions by dragging, scroll up and down to zoom in/out. But stays in one position as if you are trapped

- **Purpose** : Mimics the feel of a trackball.
- **Usage** : Freeform rotation around the scene.
- **Features** :
 - Smooth and fluid control
 - Good for object inspection

- **Note** : Less precise than **OrbitControls**
- **Drawback** : Can be disorienting for some users.

Remember this image--



“Virtual trackball” style — used often in older 3D viewers or modeling tools.

✓ Characteristics:

- You can rotate **freely in all directions** .
- You can **zoom** and **pan** .
- You can rotate the scene even **upside down** .
- Mouse movement maps to an imaginary "trackball" — intuitive, but can be unpredictable.

🔄 Rotation Behavior:

- Allows **unconstrained 360° rotation** .
- Can easily flip the camera if dragged in certain directions.

⚠ Quirks:


- Can feel "too loose" or chaotic if damping is not enabled.
- Doesn't lock the up-vector → camera up direction can spin.

3. **FlyControls**

When cursor moved(no need to drag) at center of screen, the image becomes stable else in whichever direction the cursor is the image moves ahead or forward towards that direction automatically. When you click, it moves forward a little into that particular direction the cursor aims to. One may feel as if he/she is flying with no gravity as if in space. Can't zoom in/out

- **Purpose** : Fly through the scene like a drone or first-person.
- **Usage** : Ideal for architectural walkthroughs or FPS-like movement.
- **Features** :
 - WASD or arrow key movement
 - Mouse to look around
 - **No gravity** , so camera keeps flying.

Remember this image--




4. PointerLockControls

Looks as if you are inside a shooter style game. Use mouse to look and keys to move, space to jump, exactly like in a game.

- **Purpose** : First-person shooter style controls.
- **Usage** : Use mouse to look and keys to move.
- **Requires** : Pointer Lock API (locks the mouse inside the canvas).
- **Features** :
 - Realistic FPS camera
 - Often used in games

- **Example :**

Remember this image--



- You can move forward/backward and jump using keys with **PointerLockControls** in Three.js — but not out of the box .

PointerLockControls only handles **camera orientation** (i.e., rotating the camera based on mouse movement), **not movement** like walking, jumping, or gravity. So, to get full movement (WASD + jump), you need to implement it **yourself** , typically by combining it with a **physics engine** or basic math.

✅ What **PointerLockControls** does:

- Locks the mouse to the screen (so mouse movement rotates the camera).
- Updates camera rotation based on mouse movement (like an FPS camera).
- Allows "free look" mode, similar to first-person shooters.

❌ What it does **not** do (by itself):

- Handle movement (forward, backward, strafe left/right).
- Apply physics (gravity, jump, collision).

5. **FirstPersonControls**

Like FlyControls, Simulate walking like in a first-person game

- **Purpose** : Walk through the scene like in an FPS game.
- **Usage** : Basic alternative to **PointerLockControls**.
- **Features** :
 - Mouse look
 - WASD navigation
 - Less realistic than pointer lock

Remember this image---



FlyControls vs FirstPersonControls

Feature	FirstPersonControls	FlyControls
Movement type	FPS-style: walk on the ground	Free-flying in 3D space (like a drone/spacecraft)
Gravity / vertical lock	Simulates walking; Y-axis can be constrained	No gravity; full 3D movement
Look behavior	Mouse controls look direction	Mouse controls pitch/yaw for flying
Keyboard movement	Forward, backward, left, right (WASD)	Same, plus up/down freely
Camera can fly?	No (unless lookVerticalis true)	Yes, full 6DoF flying
Roll rotation	No	Optional (not default)

Feature	FirstPersonControls	FlyControls
Use case	Walking simulators, FPS games	Drone, flight sim, space navigation

Key Differences Explained

FirstPersonControls

- Simulates human walking:
 - Movement is constrained to ground by default (like walking in a game).
 - Mouse moves the camera view (head turning).
 - Typically used in **FPS-style** games or walkthroughs.
- Has flags like:
 - `lookVertical`: whether to allow vertical mouse look.
 - `constrainVertical`: restrict vertical look range.

FlyControls

- Simulates flying or floating:
 - Camera can **move and look in any direction** , like flying a drone or spaceship.
 - Mouse controls camera pitch and yaw (fly direction).
 - Keyboard allows movement in all 3 dimensions: forward/backward, left/right, **up/down** .

Real-World Examples

Scenario	Use This Control
Walking through a virtual museum	FirstPersonControls
Exploring a space station in zero-g	FlyControls
Ground-based game character movement	FirstPersonControls
Drone simulation or aerial flyover	FlyControls

6. ArcballControls

Same like TrackballControls but no momentum or inertia after you you release the click.
Can zoom in/out

- **Purpose** : Like **OrbitControls** but with more intuitive, sphere-based rotation (like Blender).
- **Usage** : Object inspection, modeling.
- **Features** :
 - Rotate by dragging on a virtual sphere
 - Zoom and pan
- **Advanced** : Gives precise control over object rotation.

Remember this image--



Inspired by **modern 3D modeling UIs** like Blender or Maya with better camera up-vector preservation.

✓ Characteristics:

- Also allows rotation **around a pivot point** , but:
 - **Keeps the up direction fixed** (typically the Y axis).
 - Rotation is often **limited to a sphere** around the object.
- Built to avoid camera flipping or going upside down.
- Offers a **more predictable** experience, especially for casual users.

🔄 Rotation Behavior:

- Constrained, smooth orbiting around an object.
- Rotations are internally handled using **quaternions** for stability.

⚠ Quirks:

- Slightly less freedom than Trackball.
- Might feel more "locked" if you're trying to view from extreme angles.

📌 Real-World Examples

Scenario	Recommended Control
3D model viewer (full freedom)	TrackballControls
Product viewer / CAD-like	ArcballControls


7. MapControls

When drag from front to back it goes forward with inertia, and when dragged left to right, moves horizontally. That is when emulated push and pull to left or right and top and bottom (top and bottom using scrolling up and scrolling bottom), you get that exact pull/push feel with inertia.

It **disables vertical tilt** rotation by default.

- **Purpose** : Pan/zoom like a 2D map app (e.g., Google Maps).
- **Based on** : OrbitControls but restricts rotation to horizontal.
- **Features** :
 - Zoom in/out
 - Drag (pan)
 - No orbiting around a center
- **Use Case** : 2D data visualizations, map applications.

Remember this image--



What is **MapControls**?

MapControls is an **extension of OrbitControls** designed specifically to mimic the interaction model of **map applications** like Google Maps.

Key Characteristics of **MapControls**

- It **disables vertical tilt** rotation by default.
- Rotation is **constrained to horizontal orbiting** (like dragging a map).
- Panning is intuitive and dominant — like dragging a flat map around.
- Zooming behaves like zooming in/out on a map (scaling in the view plane).
- No roll or upside-down camera angles.

Real-World Examples

Scenario	Recommended Control
3D model viewer (full freedom)	TrackballControls
Product viewer / CAD-like	ArcballControls
Maps, 2D planes, top-down UIs	MapControls

Summary Table

Control Type	Best For	Allows Orbit	Allows Fly	FPS-Style	Pan	Zoom
OrbitControls	General 3D navigation	✓	✗	✗	✓	✓
TrackballControls	Smooth object inspection	✓	✗	✗	✓	✓
FlyControls	Fly-throughs, drones	✗	✓	✗	✗	✓
PointerLockControls	FPS games	✗	✓	✓	✗	✗
FirstPersonControls	Basic walking simulation	✗	✓	✓	✗	✗
ArcballControls	Precision object rotation	✓ (spherical)	✗	✗	✓	✓
MapControls	2D map-style panning/zooming	✗	✗	✗	✓	✓

Resizing

The 3d graphic needs to resize every time when the user changes the window size. So use the `aspect` property of camera. But straightaway don't do `renderer.set(window.innerWidth, window.innerHeight)` inside the `renderLoop` because this will cause a unexpected result. Instead change the aspect ratio of camera in `renderLoop`

Instead of putting inside the `renderLoop`, put inside the `resize` event of windows, coz u don't need to update the aspect ratio even when we are in the same window right and `renderLoop` happens every time we animate it in same window.

```

window.addEventListener('resize', () =>{
  camera.aspect = window.innerWidth / window.innerHeight;
  camera.updateProjectionMatrix()
  renderer.setSize(window.innerWidth, window.innerHeight);
})

// render the scene
const renderloop = () => {
  controls.update();  renderer.render(scene, camera);
}

```

```
window.requestAnimationFrame(renderloop);  
};
```

Units in Three Js

In **Three.js** , **units are arbitrary** —they don't correspond to real-world meters, centimeters, or inches. However, they are internally consistent. Here's how they work and how to interpret them:

1. Units Are Arbitrary but Consistent

You decide what **1 unit** means in your scene:

- 1 unit = 1 meter → great for architectural visualizations
- 1 unit = 1 centimeter → maybe for product design
- 1 unit = 1 foot → common in some engineering uses

Example: `new THREE.BoxGeometry(1, 1, 1) // A cube of 1x1x1 units`

→ If you say 1 unit = 1 meter, then it's a **1 meter cube**

2. Units and the Camera

Camera settings like this:

```
new THREE.PerspectiveCamera(75, aspect, 0.1, 1000)
```

- The **near** (0.1) and **far** (1000) values define what **range of units** will be visible to the camera.
- If you place an object **outside this range** , it won't be rendered.

So if you create a mesh at `position.z = 1200` but `camera.far = 1000`, it will be **invisible** .

3. Light Intensity, Distance, and Units

Light behavior depends on units too:

```
new THREE.PointLight(color, intensity, distance)
```

- **distance** is in scene units → the light fades after this distance.
- Use consistent units across your whole scene so lights behave naturally.

4. Real-World Scale Reference

For realism:

- Average human height = ~1.7–1.8 units (if 1 unit = 1 meter)
- Door height = ~2 units
- Room size = 5–10 units

This is important for accurate camera FoV and user navigation.

5. Physics Engines (like Cannon.js, Ammo.js)

If you use a physics engine, it **assumes 1 unit = 1 meter**. Scaling too large or too small can break physics simulations. Stick to:

- Object sizes ≈ 0.1 to 10 units
- Masses ≈ 0.1 to 100 kg

Summary

Concept	Interpreted Unit
<code>BoxGeometry(1,1,1)</code>	1x1x1 units (your choice: meter, cm...)
<code>camera.position.z = 10</code>	10 units away from scene origin
<code>PointLight(distance=5)</code>	Light fades after 5 units

Helpers

In **Three.js**, **helpers** are special visual aids that assist in understanding and debugging your 3D scene. They don't affect the logic or physics of your objects — they simply help **visualize positions, axes, lights, cameras, etc.**

1. AxesHelper
2. GridHelper

3. CameraHelper
4. DirectionalLightHelper
5. PointLightHelper
6. SpotLightHelper
7. HemisphereLightHelper
8. BoxHelper
9. Box3Helper
10. PlaneHelper
11. SkeletonHelper

Here's a detailed breakdown of the most commonly used helpers:

✅ 1. AxesHelper

📌 **Purpose:** Visualizes the X (red), Y (green), and Z (blue) axes.

```
const axesHelper = new THREE.AxesHelper(5); // length of the axes lines
scene.add(axesHelper);
```

- Useful for knowing orientation and direction.
- X = Red, Y = Green, Z = Blue

✅ 2. GridHelper

📌 **Purpose:** Creates a grid on the ground (like graph paper).

```
const gridHelper = new THREE.GridHelper(10, 10); // size, divisions
scene.add(gridHelper);
```

- Useful for understanding ground plane and scale.
- Can be customized to look like floor tiles.

✅ 3. CameraHelper

📌 **Purpose:** Shows the frustum (visible volume) of a camera.

```
const cameraHelper = new THREE.CameraHelper(someCamera);
scene.add(cameraHelper);
```


- Helpful when using multiple cameras or debugging camera view.

✓ 4. DirectionalLightHelper

📌 Purpose: Visualizes the direction and origin of a directional light.

```
const light = new THREE.DirectionalLight(0xffffff, 1);  
const helper = new THREE.DirectionalLightHelper(light, 5); // light length  
scene.add(helper);
```

- Shows direction with an arrow and light source location.

A **Directional Light** simulates a light source that is infinitely far away and shines light in a **single direction** , like the **sun** .

It illuminates **all objects equally from that direction** , regardless of their distance from the light.

SYNTAX---

```
const light = new THREE.DirectionalLight(color, intensity);
```

✓ 5. PointLightHelper

📌 Purpose: Displays the position and range of a point light.

```
const light = new THREE.PointLight(0xffffff, 1, 10);  
const helper = new THREE.PointLightHelper(light, 1); // sphere size  
scene.add(helper);
```

✓ 6. SpotLightHelper

📌 Purpose: Shows the spotlight cone.

```
const spotLight = new THREE.SpotLight(0xffffff);  
const helper = new THREE.SpotLightHelper(spotLight);  
scene.add(helper);
```

- Good for adjusting the angle and direction of a spotlight.

✓ 7. HemisphereLightHelper

📌 Purpose: Displays a hemisphere light as a dome and ground line.

```
const hemiLight = new THREE.HemisphereLight(0xffffbb, 0x080820, 1);  
const helper = new THREE.HemisphereLightHelper(hemiLight, 5);  
scene.add(helper);
```

✓ 8. BoxHelper

📌 Purpose: Draws a bounding box around an object.

```
const helper = new THREE.BoxHelper(object, 0xffff00);  
scene.add(helper);
```

- Dynamically updates if the object moves.

✓ 9. Box3Helper

📌 Purpose: Visualizes a static bounding box.

```
const box = new THREE.Box3().setFromObject(mesh);  
const helper = new THREE.Box3Helper(box, 0xff0000);  
scene.add(helper);
```

✓ 10. SkeletonHelper

📌 Purpose: Shows bones in a skinned mesh (used in animations).

```
const helper = new THREE.SkeletonHelper(skinnedMesh);  
scene.add(helper);
```

- Useful for debugging rigging and animations.

✓ 11. PlaneHelper

📌 Purpose: Visualizes a mathematical plane.

```
const plane = new THREE.Plane(new THREE.Vector3(1, 0, 0), 0);
const helper = new THREE.PlaneHelper(plane, 5, 0xffff00);
scene.add(helper);
```

In Three.js, `THREE.Plane` and `THREE.PlaneHelper` are useful when you want to work with **infinite mathematical planes** —like for clipping, debugging geometrical calculations, or visualizing space divisions.

◆ `THREE.Plane`

A `Plane` in Three.js is a **mathematical concept**, not a visible object. It represents an infinite flat surface defined by:

```
const plane = new THREE.Plane(normal, constant);
```

◆ Parameters:

- `normal`: `THREE.Vector3` — direction **perpendicular to the plane**.
- `constant`: `Number` — the **distance from the origin** (along the normal vector) to the plane.

For example:

`new THREE.Plane(new THREE.Vector3(1, 0, 0), 0)` creates a vertical plane that lies along the YZ plane ($X = 0$).

◆ `THREE.PlaneHelper`

A `PlaneHelper` is a **visible representation** of the mathematical `Plane`.

```
const helper = new THREE.PlaneHelper(plane, size, color); // *PSC
scene.add(helper);
```

◆ Parameters:

- `plane`: the `THREE.Plane` to visualize.
- `size`: visual length of the plane helper (it's finite for visualization).
- `color`: optional — color of the helper.

✓ Example

```
const plane = new THREE.Plane(new THREE.Vector3(1, 0, 0), 0); // Plane X = 0
const helper = new THREE.PlaneHelper(plane, 5, 0xffff00);      // Yellow plane,
length 5
scene.add(helper);
```

This creates a **yellow helper** that represents a vertical plane aligned with the YZ axis, going through the origin.



Updating Helpers

Some helpers (like **SpotLightHelper**) need to be manually updated if the light changes:

```
spotLightHelper.update();
```



Summary Table

Helper	Purpose
AxesHelper	Shows X/Y/Z axes
GridHelper	Displays a floor/grid
CameraHelper	Visualizes camera view/frustum
DirectionalLightHelper	Shows direction light angle
PointLightHelper	Shows point light position and range
SpotLightHelper	Visualizes spotlight cone
HemisphereLightHelper	Shows hemisphere light source
BoxHelper	Bounding box around object
Box3Helper	Static box visualization
SkeletonHelper	Shows animation bone structure
PlaneHelper	Visualizes a mathematical plane

Object3D

In **Three.js** , **Object3D** is the **base class** for almost everything that appears in a 3D scene, including:

- **Mesh**
- **Group**
- **Camera**
- **Light**
- **Scene**
- and even empty objects for transformations

If you understand **Object3D**, you understand the **foundation** of Three.js’s scene graph system.

What is **Object3D**?

Object3D is a **hierarchical node** in a 3D scene — it can:

- Store **position** , **rotation** , and **scale**
- Have **children** and a **parent**
- Be **transformed** (moved, rotated, scaled)
- Be **rendered** if it’s a visible type (like a **Mesh**) or used for organization only (like a **Group**)

Constructor

```
const obj = new THREE.Object3D();
```


Key Properties



Property	Type	Description
.position	Vector3	Position in local space (default: (0, 0, 0))
.rotation	Euler	Rotation in radians (x, y, z)
.quaternion	Quaternion	Rotation in quaternion form (alternative to .rotation)
.scale	Vector3	Scale factors (default: (1, 1, 1))
.up	Vector3	Up direction for the object (default: (0, 1, 0))

Property	Type	Description
<code>.visible</code>	Boolean	Whether the object is visible
<code>.children</code>	Array<Object3D>	Array of child objects
<code>.parent</code>	Object3D	Reference to parent (if any)
<code>.matrix</code>	Matrix4	Local transformation matrix
<code>.matrixWorld</code>	Matrix4	Global/world transformation matrix
<code>.name</code>	String	Optional name to identify the object
<code>.uuid</code>	String	Unique ID assigned automatically

`.rotation`

Rotation is around a particular axis. Hence sometime we can't make out the difference in before and after of a rotation esp in case of cube.





Values--

- `cube.rotation.x = 10` --You are telling it to rotate to 10 degrees
- Can use `Math.PI`--- `cube.rotation.x = Math.PI * 0.5` --You are telling it to rotate to 90 degrees
- Can use +/- values for clockwise or anticlockwise directions
- Can use `Three.degToRad()` ThreeJs 's own Utility function ---
`cube.rotation.x = Three.degToRad(90)` --You are telling it to rotate to 90 degrees

Order of rotation operations---

- The order is important ie

```
cube.rotation.x = Three.degToRad(90);
cube.rotation.z = Three.degToRad(45);
//The above and the below resulted look will be different coz the order is different
cube.rotation.x = Three.degToRad(90);
cube.rotation.z = Three.degToRad(45);
```

- Hence we use `.reorder()` method eg--- `cube.rotation.reorder('XYZ');`
The string passed depends on the order of axes -- X, Y, Z in caps ie--

```
cube.rotation.reorder('YXZ') // DO THIS BEFORE APPLYING ROTATIONS
cube.rotation.x = Three.degToRad(90);
cube.rotation.z = Three.degToRad(45);
//Now you can move the cube.rotation codes anywhere and be ensured that the order would remain same
```

◆ Key Methods

Method	Description
<code>.add(child)</code>	Adds a child <code>Object3D</code>
<code>.remove(child)</code>	Removes a child
<code>.traverse(callback)</code>	Recursively visits this object and all descendants
<code>.traverseVisible(callback)</code>	Same as <code>traverse</code> , but skips invisible objects
<code>.getObjectByName(name)</code>	Searches for a descendant with a given name
<code>.getWorldPosition(target)</code>	Copies world position into target vector
<code>.getWorldQuaternion(target)</code>	Copies world rotation (quaternion)
<code>.getWorldScale(target)</code>	Copies world scale

🕒 Transformation

Method	Description
<code>.lookAt(vector)</code>	Rotates object to face a point in world space
<code>.translateX/Y/Z(distance)</code>	Moves object along its local X, Y, or Z axis

Method	Description
<code>.rotateX/Y/Z(angle)</code>	Rotates object around its local axis
<code>.applyMatrix4(matrix)</code>	Applies a transformation matrix
<code>.updateMatrix()</code>	Updates local matrix from position/rotation/scale
<code>.updateMatrixWorld(force)</code>	Updates global matrix
<code>.localToWorld(vec3)</code>	Converts local to world space
<code>.worldToLocal(vec3)</code>	Converts world to local space

Real-Life Analogy

Imagine a **robot arm** with joints:

- The **shoulder** , **elbow** , and **hand** are each `Object3Ds`.
- Rotating the **shoulder** affects all the child joints.
- This is how parent-child hierarchies work.

Usage Examples

Grouping Objects

```
const group = new THREE.Object3D();
group.add(mesh1, mesh2);
scene.add(group);
group.position.set(0, 5, 0);

//BTW The aboe code is same as below (Just FYI)

const group = new THREE.Group();
group.add(mesh1, mesh2);
scene.add(group);
group.position.set(0, 5, 0);

//Will See Group later..
```

`THREE.Group` is a subclass of `THREE.Object3D` with no additional functionality.

It's just a **semantic** alias used to improve readability when grouping objects. Internally, it **inherits everything** from `Object3D`.

So you can think of it like:

```
class Group extends Object3D {}
```

Empty Parent for Rotation

```
const pivot = new THREE.Object3D();  
pivot.add(camera);  
scene.add(pivot);  
  
pivot.rotation.y = Math.PI / 2; // rotates camera around origin
```

.position

- It returns a Vector3 Object

You can use **.position** to:

- **get** the current position vector
- **modify** it directly using **.set(x, y, z)** or arithmetic operations

Quick Notes:

- **.position** is a **Vector3** object → not just raw coordinates.
- This means you can do:

```
cube.position.add(new THREE.Vector3(1, 0, 0));
```

to move it right by 1 unit.

---- **camera.position.x = 5** We could set any Object3D child like camera's position by single oordinate this way because, **.position** returns Vector3D Object which has it's own properties---> x, y z, isVector3, etc

Using **Vector3 .copy()** method by accessing **.position** property of **Object3D**-----

```

4 // initialize the scene
5 const scene = new THREE.Scene();
6
7 // add objects to the scene
8 const cubeGeometry = new THREE.BoxGeometry(1, 1, 1);
9 const cubeMaterial = new THREE.MeshBasicMaterial({ color: "red" });
10 const cubeMesh = new THREE.Mesh(cubeGeometry, cubeMaterial);
11 scene.add(cubeMesh);
12
13 const tempVector = new THREE.Vector3(0, 3, 0)
14 cubeMesh.position.copy(tempVector)
15
16 const axesHelper = new THREE.AxesHelper(2);
17 scene.add(axesHelper);
18

```

Now this is another way to move the mesh 3 units up (towards y-axis)

.scale

To inc/dec size of any of the size of faces along the axis. Scale factors (default: (1, 1, 1)).

Eg--

```

cubemsh.scale.x = 2 // scale x faces by 2 times
cubemesh.scale.set(3,2,2,) // scale x,y,z faces. Can use .set() coz .scale returns
Vector3 object which btw has .set() method

```

🧠 Tip

- Use **Object3D** or **Group** for **pivot points** , **scene organization** , or **non-visible logic** .
- You can **nest** as many **Object3Ds** as you want to build complex hierarchies.

Example-

```

import * as THREE from 'three';

// Setup scene, camera, renderer
const scene = new THREE.Scene();
const camera = new THREE.PerspectiveCamera(75, window.innerWidth/window.innerHeight,
0.1, 1000);
camera.position.z = 10;

const renderer = new THREE.WebGLRenderer({ antialias: true });
renderer.setSize(window.innerWidth, window.innerHeight);

```

```
document.body.appendChild(renderer.domElement);

// Create a parent group
const parentGroup = new THREE.Object3D();
parentGroup.name = "parentGroup";
scene.add(parentGroup);

// Create two cubes
const geometry = new THREE.BoxGeometry();
const material1 = new THREE.MeshBasicMaterial({ color: 'red' });
const material2 = new THREE.MeshBasicMaterial({ color: 'green' });

const cube1 = new THREE.Mesh(geometry, material1);
cube1.name = "cube1";
cube1.position.x = -2;

const cube2 = new THREE.Mesh(geometry, material2);
cube2.name = "cube2";
cube2.position.x = 2;

// Add cubes to group
parentGroup.add(cube1, cube2);

// Move the entire group to the right
parentGroup.translateX(1); // equivalent to parentGroup.position.x += 1

// Rotate the group on X axis
parentGroup.rotateX(Math.PI / 8);

// Traverse all objects (including invisible)
parentGroup.traverse(obj => {
  console.log(`Found: ${obj.name}, Visible: ${obj.visible}`);
});

// Hide one cube and use traverseVisible
cube2.visible = false;

parentGroup.traverseVisible(obj => {
  console.log(`Visible only: ${obj.name}`);
});

// Remove cube2 after 2 seconds
setTimeout(() => {
  parentGroup.remove(cube2);
  console.log("Removed cube2 from the group");
}, 2000);

// Find cube1 by name
const found = parentGroup.getObjectByName("cube1");
console.log("Found by name:", found);

// Animate
function animate() {
  requestAnimationFrame(animate);

  cube1.rotation.y += 0.01;

  renderer.render(scene, camera);
}
```

```
}  
animate();
```

Vector3 - II

`.position.x`, `.position.y` , `.position.z` --- Written above inside Object3D topic

`.distanceTo()`

The `.distanceTo()` method is a **Vector3 method** in Three.js, used to compute the **Euclidean distance** between two 3D points.

✓ Syntax

```
vectorA.distanceTo(vectorB)
```

📌 Parameters

- `vectorB`: A `THREE.Vector3` object.
- Returns: A `Number` representing the straight-line (Euclidean) distance between `vectorA` and `vectorB`.

📄 Example

```
const pointA = new THREE.Vector3(0, 0, 0);  
const pointB = new THREE.Vector3(3, 4, 0);  
  
const distance = pointA.distanceTo(pointB);  
console.log(distance); // 5
```

🧠 Real-Life Use Cases

- Distance between camera and object
- Triggering actions when two objects are close
- Calculating proximity-based effects like fading, gravity, or selection radius

Example 2-- (using `.copy()` and `.distanceTo()`)

```

4 // initialize the scene
5 const scene = new THREE.Scene();
6
7 // add objects to the scene
8 const cubeGeometry = new THREE.BoxGeometry(1, 1, 1);
9 const cubeMaterial = new THREE.MeshBasicMaterial({ color: "red" });
10 const cubeMesh = new THREE.Mesh(cubeGeometry, cubeMaterial);
11 scene.add(cubeMesh);
12
13 const tempVector = new THREE.Vector3(0, 0, 0)
14 cubeMesh.position.copy(tempVector)
15
16 const axesHelper = new THREE.AxesHelper(2);
17 scene.add(axesHelper);
18
19 // initialize the camera
20 const camera = new THREE.PerspectiveCamera(
21     35,
22     window.innerWidth / window.innerHeight,
23     0.1,
24     200
25 );
26 camera.position.z = 5;
27
28 console.log(cubeMesh.position.distanceTo(camera.position))
29 )

```

Here `console.log(cubeMesh.position.distanceTo(camera.postion))` will give 5 coz distance from (0,0,0) to 5 units on z is 5.

Group

Group is just a **semantic** alias used to improve readability when grouping objects. Internally, it **inherits everything** from `Object3D`.

So you can think of it like:

```
class Group extends Object3D {}
```

Example

■ Using `THREE.Object3D`

```

const group = new THREE.Object3D();
group.add(mesh1, mesh2);
scene.add(group);
group.position.set(0, 5, 0);

```

■ Using **THREE.Group**

```
const group = new THREE.Group();
group.add(mesh1, mesh2);
scene.add(group);
group.position.set(0, 5, 0);
```

✅ When to use which?

Use Object3D if...	Use Group if...
You want a generic container	You want to organize/group objects
You're doing something abstract like attaching a camera/light	You're grouping meshes logically

They both support:

- **.position**, **.rotation**, **.scale**
- **.add()**, **.remove()**
- **.traverse()**, **.lookAt()**
- parenting behavior


Scene Hierarchy

Children of a parent mesh/group will inherit the properties or transformational properties of the parent/mesh. So for example the children scale property for example depends on the parent scale ie would have that as the base scale, but the child can then inc/dec scale independantly


- When we set a position/scale of an object, we are setting its LOCAL SCALE /POSITION. THIS WOULD BE RELATIVE TO ITS OWN LOCAL COORDINATE SYSTEM

THE LOCAL COORDINATE SYSTEM IS INHERITED FROM THE PARENT


EXAMPLE---




In the above code, the position of cubeMesh, cubeMesh2, cubeMesh3 are relative to its own container ie group



Here the scale of all the mesh inside the group is doubled



Here the y position of all the mesh inside the group is increased by 2 units +
Position of cubeMesh is decreased by in 1 unit in the y axis



Here the scale of cubeMesh increased by 0.5 units into x, y, z axis (using
setScale()) + Scale of group increased by 2 units into x, y, z axis

Three.js uses a **scene graph** to represent and manage all 3D content in a structured way. This graph is hierarchical — objects can be **parents** or **children**, forming a tree-like structure.

Another Example--

```
const scene = new THREE.Scene();

const group = new THREE.Group();
scene.add(group); // Group is a child of the Scene

const cube = new THREE.Mesh(new THREE.BoxGeometry(), new THREE.MeshBasicMaterial());
const sphere = new THREE.Mesh(new THREE.SphereGeometry(), new
THREE.MeshBasicMaterial());

group.add(cube, sphere); // Both are children of the group
cube.add(new THREE.PointLight()); // Light is child of the cube
```

Transformations **propagate** down the hierarchy--

```
group.position.set(5, 0, 0);
cube.position.set(1, 0, 0);
```

The cube's final world position becomes:

```
group.position + cube.position = (5, 0, 0) + (1, 0, 0) = (6, 0, 0)
```

6. Traversing the Graph

You can access all children using `.children`, or loop with `.traverse()`:

```
scene.traverse(object => {
  if (object.isMesh) object.material.wireframe = true;
});
```

This code **recursively visits every object** in the `scene` (and all its children and sub-children), and for every object that is a **mesh**, it enables **wireframe rendering** for its material.

```
object.material.wireframe = true;
```

- For every mesh, it changes the material to render in **wireframe mode** (i.e., only edges, no filled surfaces).

Example Before and After

Without `wireframe = true`:

You see a solid 3D cube.

With `wireframe = true`:

You see a mesh "cage" — only the edges of the cube are visible.

When would you use this?

- **Debugging geometry** (to see how complex or dense a model is)
- **Stylized visual effects**
- **Temporarily disabling textures/materials for inspection**

Common Classes in the Hierarchy

Class	Inherits From	Used For
Scene	Object3D	Root node
Group	Object3D	Logical grouping
Mesh	Object3D	3D objects
Camera	Object3D	Viewpoints
Light	Object3D	Lighting
AxesHelper, etc.	Object3D	Visual debugging tools

5. Why This Matters

Feature	Benefit
Grouping objects	Organize complex scenes
Parent-child transforms	Easy animation and control
Camera following an object	Attach camera to a player
Light tied to a moving object	Example: flashlight effect

Euler

In **Three.js** , **Euler** is a class used to **represent 3D rotation** around the X, Y, and Z axes.

1. What is an Euler rotation?

A rotation in 3D space **defined by three angles** , each describing a rotation around one of the axes — usually **X** , **Y** , and **Z** — **in a specific order** .

Imagine tilting your head:

- Rotate left/right → Y-axis
- Look up/down → X-axis
- Tilt head sideways → Z-axis

These are Euler-style rotations.

2. Constructor Syntax

```
const euler = new THREE.Euler(x, y, z, order);
```

- **x, y, z**: Angles in **radians** .
- **order**: (*optional*) A string defining the rotation order. Default: **"XYZ"**

3. Common Rotation Orders

- **"XYZ"** (default)
- **"YXZ"**
- **"ZXY"**
- **"ZYX"**
- **"YZX"**
- **"XZY"**

Each rotation order gives **different results** , because rotations are **not commutative** .

4. Properties

Property	Type	Description
x	Number	Rotation around X-axis (in radians)
y	Number	Rotation around Y-axis

Property	Type	Description
<code>z</code>	Number	Rotation around Z-axis
<code>order</code>	String	Order of rotation axes ('XYZ', etc.)
<code>isEuler</code>	Boolean	Always true — useful for type checking

5. Methods

Method	Description
<code>.set(x, y, z, order?)</code>	Sets all values manually
<code>.clone()</code>	Returns a copy of this Euler
<code>.copy(euler)</code>	Copies values from another Euler
<code>.equals(euler)</code>	Compares with another Euler
<code>.setFromRotationMatrix(matrix4, order?)</code>	Converts a rotation matrix to Euler
<code>.setFromQuaternion(q, order?)</code>	Converts a quaternion to Euler
<code>.toVector3()</code>	Returns a Vector3 (x, y, z)
<code>.reorder(order)</code>	Reorders the Euler angles (risk of gimbal lock!)

6. Example Usage

```
const object = new THREE.Mesh(geometry, material);
object.rotation.x = Math.PI / 4; // 45 degrees
object.rotation.set(Math.PI / 4, Math.PI / 4, 0);

// Access Euler object directly
console.log(object.rotation instanceof THREE.Euler); // true
```

7. Gimbal Lock

Gimbal Lock occurs when two rotation axes align, causing a degree of freedom to be lost.

- Euler rotations can suffer from gimbal lock.

- Use **Quaternion** if you want smooth, continuous 3D rotation (e.g. for cameras, ships).

8. Euler vs Quaternion

Feature	Euler	Quaternion
Intuitive	✅ Easy to understand (X/Y/Z)	❌ Less intuitive math
Gimbal Lock	❌ Can suffer from it	✅ Immune
Animation	✅ OK for simple	✅ Best for smooth rotation
Performance	✅ Faster for basic transforms	Slightly heavier

Animations

Animation in **Three.js** is the process of updating object properties (like position, rotation, scale, color, etc.) over time to create motion or visual change.

1. Types of Animation in Three.js

Type	Description
Manual animation loop	Custom animation logic via <code>requestAnimationFrame()</code>
Object3D transformations	Animate position, rotation, scale manually
<code>THREE.Clock</code>	Used to track time deltas between frames
Keyframe tracks & <code>AnimationMixer</code>	For predefined model animations (like glTF)
GSAP or <code>Tween.js</code>	External animation libraries for smoother transitions

2. Basic Animation Loop

The simplest animation loop looks like this:

```
function animate() {  
  requestAnimationFrame(animate);  
}
```

```
// update object properties
cube.rotation.y += 0.01;

// render the scene
renderer.render(scene, camera);
}
animate();
```

- `requestAnimationFrame` ensures the browser runs at ~60fps.
- Use `.rotation`, `.position`, `.scale`, or material properties inside.

3. Using `THREE.Clock`

```
const clock = new THREE.Clock();

function animate() {
  const delta = clock.getDelta(); // seconds since last frame

  cube.rotation.y += delta; // time-based animation
  renderer.render(scene, camera);
  requestAnimationFrame(animate);
}
```

Why use `Clock`?

- **Frame-rate independent** animation — smooth on all systems.

Example--

```
const clock = new THREE.Clock()
let previousTime = 0

// render the scene
const renderloop = () => {
  const currentTime = clock.getElapsedTime()
  const delta = currentTime - previousTime
  previousTime = currentTime

  cubeMesh.rotation.y += THREE.MathUtils.degToRad(1) * delta * 20

  cubeMesh.scale.x = (Math.sin(currentTime)) * 20 + 2
  cubeMesh.position.x = (Math.sin(currentTime)) + 2


  controls.update();
  renderer.render(scene, camera);
  window.requestAnimationFrame(renderloop);
};
```

In the above example if we would have written for example-

`cubeMesh.position.x = 0.5 * delta` , it would animate abruptly and soon it will go out of screen. Because the values are increasing LINEARLY and graphs to high values. Hence we need CYCLIC VALUES

Therefore we use `Math.sin()`

Since multiplying sine value means its x times the sine value which would be the amplitude. Adding by 1 or 2 allows you to get values between 0-2/0-3 so that there would be good animations



4. `AnimationMixer` for glTF / FBX animations

When using 3D models with predefined animations (like `.gltf` or `.fbx` files):

```
const loader = new GLTFLoader();
loader.load('model.gltf', (gltf) => {
  const model = gltf.scene;
  scene.add(model);

  const mixer = new THREE.AnimationMixer(model);
  const action = mixer.clipAction(gltf.animations[0]);
  action.play();

  animate();

  function animate() {
    const delta = clock.getDelta();
    mixer.update(delta);
    renderer.render(scene, camera);
  }
});
```



```
    requestAnimationFrame(animate);
  }
});
```

- **AnimationMixer** updates animations over time.
- **clipAction()** picks which animation to play.

🔧 5. External Animation Libraries (Optional)

- **GSAP** — Smooth, professional-grade animation
- **Tween.js** — Simple tweening system

Example with GSAP:

```
gsap.to(cube.position, {
  x: 5,
  duration: 2,
  ease: "power1.inOut"
});
```

🧰 6. Helper: **.matrixAutoUpdate**

If you're doing **manual matrix transformations** (rare):

```
mesh.matrixAutoUpdate = false;
mesh.matrix.makeTranslation(2, 3, 4);
mesh.updateMatrix();
```

🎯 Animation Targets

Target	Commonly Animated Properties
Mesh	<code>.position</code> , <code>.rotation</code> , <code>.scale</code> , <code>.material.color</code>
Camera	<code>.position</code> , <code>.lookAt()</code>
Lights	<code>.intensity</code> , <code>.position</code> , <code>.color</code>
Material	<code>.opacity</code> , <code>.color</code> , <code>.wireframe</code>

💡 Best Practices

- Use `delta` from `Clock` for **consistent speed** .
- Group objects using `Object3D` if animating together.
- Offload complex animations to `AnimationMixer` or GSAP.

BufferGeometry - 2

In `Three.js` , `BufferGeometry` is the **core class used to represent and render geometric shapes** in the most memory-efficient and performance-optimized way.

- It's the low-level, modern alternative to the older `Geometry` class (which has been removed from recent versions of `Three.js`).

What is `BufferGeometry`?

A structure that stores geometry data (like positions, normals, UVs, colors) in **typed arrays** using **buffer attributes** .

Everything you see in 3D (a cube, sphere, custom shape) is made up of:

- **Vertices**
- **Faces (triangles)**
- **Normals**
- **UVs (for texture mapping)**
- **Colors**

These are packed into **buffers** for fast GPU rendering.

2. Anatomy of BufferGeometry

```
const geometry = new THREE.BufferGeometry();

const vertexPoints = new Float32Array([
  0, 0, 0,    // vertex 1
  1, 0, 0,    // vertex 2
  0, 1, 0     // vertex 3
]);

geometry.setAttribute('position', new THREE.BufferAttribute(vertexPoints, 3));
```

- **Float32Array**: Typed array of floats
- **.setAttribute('position', ...)**: Defines vertex positions
- The **3** means each vertex has 3 components (x, y, z)

BufferAttribute

This class stores data for an attribute (such as vertex positions, face indices, normals, colors, UVs, and any custom attributes) associated with a BufferGeometry, which allows for more efficient passing of data to the GPU.

What is BufferAttribute?

A way to store and organize attribute data (like positions, normals, UVs) in a structured form for rendering.

Think of it like this:

```
new THREE.BufferAttribute(typedArray, itemSize)
```

- **typedArray**: Flat array of numbers (e.g. **Float32Array**)
- **itemSize**: Number of elements per vertex (e.g. 3 for **x,y,z**)

Example: Storing Vertex Positions

```
const attr = new THREE.BufferAttribute(  
  new Float32Array([...]), // typed array  
  3,                       // itemSize  
  false                    // normalized (optional)  
);
```

Important Properties of BufferAttribute

Property	Description
.array	The underlying TypedArray
.count	Number of items (vertices = array.length / itemSize)
.itemSize	Number of values per item (e.g., 3 for x,y,z)
.normalized	Whether values should be normalized to [0–1]

Property	Description
<code>.needsUpdate</code>	Must set <code>true</code> if you update values manually
<code>.usage</code>	Buffer usage hint (e.g. <code>DynamicDrawUsage</code>)

Useful Methods of BufferAttribute

Method	What it does
<code>.setX(index, value)</code>	Set x value of item at given index
<code>.setY(index, value)</code>	Set y value
<code>.setZ(index, value)</code>	Set z value
<code>.setXYZ(index, x, y, z)</code>	Set x, y, z of one vertex
<code>.getX(index)</code>	Get x value of item
<code>.copy()</code>	Clone the attribute
<code>.copyAt(i1, attr2, i2)</code>	Copy item from another attribute
<code>.applyMatrix4(matrix)</code>	Apply transformation to each vertex
<code>.clone()</code>	Deep copy of attribute
<code>.toJSON()</code>	Serialize to JSON

Dynamic BufferAttributes

If you update values each frame (e.g., in animations), do this:

```
positionAttribute.needsUpdate = true;
```

And if you're frequently changing data:

```
positionAttribute.setUsage(THREE.DynamicDrawUsage);
```

Common Attributes

Attribute	Purpose
<code>position</code>	Vertex positions (required)

Attribute	Purpose
normal	Per-vertex normals (for lighting)
uv	Texture coordinates (2D)
color	Per-vertex colors (optional)
index	Index buffer (to reuse vertices)

Example--

```
const geometry = new THREE.BufferGeometry();

// 🌈 Per-vertex colors
const colors = new Float32Array([
  1, 0, 0, // Red
  0, 1, 0, // Green
  0, 0, 1  // Blue
]);
geometry.setAttribute('color', new THREE.BufferAttribute(colors, 3))
```

🔧 Useful Methods

Method	Purpose
.setAttribute(name, bufferAttribute)	Add position, normal, uv, etc.
.setIndex(array)	Set index buffer
.getAttribute(name)	Get attribute (e.g. position)
.rotateX/Y/Z(angle)	Rotate geometry
.translate(x, y, z)	Move geometry
.scale(x, y, z)	Scale geometry
.center()	Centers geometry at origin
.computeVertexNormals()	Auto-generates normals (if not present)
.computeBoundingBox()	Calculates bounding box
.computeBoundingSphere()	Calculates bounding sphere

🔧 Example — Triangle

```

const geometry = new THREE.BufferGeometry();

const vertices = new Float32Array([
  0, 0, 0,
  1, 0, 0,
  0, 1, 0
]);

geometry.setAttribute('position', new THREE.BufferAttribute(vertices, 3));

const material = new THREE.MeshBasicMaterial({ color: 0xff0000, wireframe: true });
const triangle = new THREE.Mesh(geometry, material);
scene.add(triangle);

```

Example: Custom Geometry with position, normal, and color:

```

import * as THREE from 'three';
import { OrbitControls } from 'three/examples/jsm/controls/OrbitControls.js';

const scene = new THREE.Scene();

// 📷 Camera
const camera = new THREE.PerspectiveCamera(75, window.innerWidth /
window.innerHeight, 0.1, 100);
camera.position.z = 2;

// 🖼️ Renderer
const renderer = new THREE.WebGLRenderer({ antialias: true });
renderer.setSize(window.innerWidth, window.innerHeight);
document.body.appendChild(renderer.domElement);

// 🎮 Controls
const controls = new OrbitControls(camera, renderer.domElement);
controls.enableDamping = true;

// ▲ Triangle Geometry
const geometry = new THREE.BufferGeometry();

// ● Define 3 vertices (triangle)
const positions = new Float32Array([
  0, 1, 0,    // Vertex 1
  -1, -1, 0,  // Vertex 2
  1, -1, 0    // Vertex 3
]);
geometry.setAttribute('position', new THREE.BufferAttribute(positions, 3));

// ☀️ Normals (all pointing +Z for flat surface facing camera)
const normals = new Float32Array([
  0, 0, 1,
  0, 0, 1,
  0, 0, 1
]);
geometry.setAttribute('normal', new THREE.BufferAttribute(normals, 3));

```

```
// 🌈 Per-vertex colors
const colors = new Float32Array([
  1, 0, 0, // Red
  0, 1, 0, // Green
  0, 0, 1, // Blue
]);
geometry.setAttribute('color', new THREE.BufferAttribute(colors, 3));

// 🧠 Material using vertex colors + lighting
const material = new THREE.MeshStandardMaterial({
  vertexColors: true, // <-- use color attribute
  side: THREE.DoubleSide
});

const mesh = new THREE.Mesh(geometry, material);
scene.add(mesh);

// 💡 Light
const light = new THREE.DirectionalLight(0xffffff, 1);
light.position.set(2, 2, 2);
scene.add(light);

// 🔄 Animation loop
function animate() {
  requestAnimationFrame(animate);
  controls.update();
  renderer.render(scene, camera);
}
animate();
```

📦 Built-in Geometries use BufferGeometry

All built-in shapes (like `BoxGeometry`, `SphereGeometry`) are actually `BufferGeometry`:

```
const geometry = new THREE.BoxGeometry(); // Internally extends BufferGeometry
console.log(geometry instanceof THREE.BufferGeometry); // true
```

📁 8. When to use?

When?	Why?
Custom shapes	Fine control over vertex data
Dynamic geometry	Update attributes manually on the fly
Performance-critical rendering	Lower memory + faster GPU access

Materials vs texture

In **Three.js** , both **materials** and **textures** are used to define how 3D objects appear—but they serve **different purposes** :

Materials — The *"Skin"* of 3D Objects

Materials control **how light interacts** with an object.

They define:

- Color
- Shininess
- Reflectivity
- Transparency
- Wireframe rendering
- Whether to use lighting or not

Examples of material types in Three.js:

Material Type	Description
<code>MeshBasicMaterial</code>	No lighting, flat color or texture
<code>MeshStandardMaterial</code>	PBR-based, supports metalness & roughness
<code>MeshPhongMaterial</code>	Classic lighting with specular highlights
<code>MeshLambertMaterial</code>	Basic diffuse lighting
<code>MeshPhysicalMaterial</code>	More advanced than <code>Standard</code> , includes clearcoat, sheen, etc.
<code>MeshToonMaterial</code>	For cartoon/anime-style shading
<code>PointsMaterial</code> , <code>LineBasicMaterial</code>	For particles/lines

Textures — The *"Paint"* on Materials

Textures are **images** or **data** that you apply to materials to add surface detail.

They affect:

- Color (diffuse map)
- Surface bumpiness (bump/normal map)
- Roughness/metalness (for PBR)
- Transparency (alpha map)
- Glow (emissive map)

📌 You apply textures **through materials** :

```
const texture = new THREE.TextureLoader().load('wood.jpg');
const material = new THREE.MeshStandardMaterial({
  map: texture    // ← applying texture to material
});
```

🔄 Relationship Summary

-  **Materials** define *how* the object looks and reacts to light.
-  **Textures** are image-based **inputs** used *inside* materials to define visual detail.

🔍 Real-Life Analogy

Imagine you're designing a chair:


- **Material** is the *type of surface* — matte plastic, shiny metal, soft cloth.
- **Texture** is the *image/graphic pattern* on it — like wood grain, leather cracks, or camo print.

Materials

◆ Common Material Types

Material Class	Description
<code>MeshBasicMaterial</code>	Unlit, flat colors or textures. Fastest.
<code>MeshStandardMaterial</code>	PBR-based, reacts to light realistically (metalness + roughness).
<code>MeshPhysicalMaterial</code>	Extension of <code>StandardMaterial</code> with added realism (clearcoat, sheen, etc.)
<code>MeshPhongMaterial</code>	Shiny surfaces with specular highlights.

Material Class	Description
MeshLambertMaterial	Diffuse-only lighting (no shiny reflections).
MeshToonMaterial	Stylized shading for cartoon/anime effects.
MeshDepthMaterial	A material for drawing geometry by depth. Depth is based off of the camera near and far plane. White is nearest, black is farthest.
ShaderMaterial	Fully customizable with GLSL shaders.
RawShaderMaterial	Same as ShaderMaterial but with manual setup.
PointsMaterial	For rendering particles.
LineBasicMaterial/LineDashedMaterial	For lines and wireframes.



MeshDepthMaterial----


A material for drawing geometry by depth. Depth is based off of the camera near and far plane. White is nearest, black is farthest.

`THREE.MeshDepthMaterial` is a special material in **Three.js** that renders the **depth** (distance from the camera) of a mesh instead of its color or texture. It's commonly used in:

- **Shadow mapping**
- **Post-processing (e.g., depth of field)**
- **Debugging or visualizing scene depth**

✏ How Depth is Rendered----

- **Near objects** → rendered as **black** (0.0)
- **Far objects** → rendered as **white** (1.0)
- Intermediate depths are shades of gray between black and white



◆ Important Material Properties

Here's a list of **universal or commonly used** properties:

Property	Description
<code>color</code>	Base color (ignored if <code>map</code> is set).
<code>map</code>	Diffuse texture map.

Property	Description
<code>opacity</code>	0 to 1, requires <code>transparent: true</code> .
<code>transparent</code>	Enables transparency support.
<code>side</code>	<code>THREE.FrontSide</code> (default), <code>BackSide</code> , <code>DoubleSide</code> .
<code>fog</code>	The <code>.fog</code> property determines whether the material reacts to the scene's fog settings (<code>scene.fog</code>). If <code>true</code> , the material will fade out based on the camera's distance , using the fog settings. Also [FOG] for details
<code>wireframe</code>	Render as wireframe.
<code>visible</code>	Show/hide the material.
<code>alphaMap</code>	Controls transparency per pixel.
<code>depthTest/depthWrite</code>	Control z-buffer behavior.
<code>blending</code>	Controls how the material blends (additive, subtractive, etc.)

`.side`

In **Three.js**, the `.side` property is used in **materials** to control **which side(s)** of a mesh's geometry should be rendered — front, back, or both.

✅ Why `.side` Is Important

By default, Three.js **only renders the front side** of faces. If you look at a mesh from the inside, it may appear **invisible** — because the back faces aren't drawn. The `.side` property lets you change that behavior.

These are constants from **THREE**:

Value	Constant	Description
0	<code>THREE.FrontSide</code>	**(default)** Only front-facing sides are rendered.
1	<code>THREE.BackSide</code>	Only back-facing sides are rendered.
2	<code>THREE.DoubleSide</code>	Both front and back sides are rendered.

🔄 How It Works (Internally)

Three.js uses the **winding order** of triangle vertices (clockwise or counter-clockwise) to determine which side is the **front**. This is known as **backface culling** — it avoids rendering faces not visible to the camera for performance.

💡 Example

```
const material = new THREE.MeshBasicMaterial({
  color: 'orange',
  side: THREE.DoubleSide // Actually the value of constant THREE.DoubleSide is
  2
});
```

This will render both the front and back of the geometry's faces.

🔧 Example Use Case

```
const geometry = new THREE.PlaneGeometry(5, 5);
const material = new THREE.MeshStandardMaterial({
  color: 0x00ff00,
});
material.side = THREE.DoubleSide // Makes the plane visible from both sides

const plane = new THREE.Mesh(geometry, material);
scene.add(plane);
```

👉 You may wonder why is it only for planes, that the side property used well it's because for a cube the backside of the cube is actually the inside of the cube everything else is technically its front side so that's why you can see a cube from all angles or the box from all angles but the plane geometomry the actual backside is just right behind it


⚠️ Performance Note

`THREE.DoubleSide` may cause **performance hits** in complex scenes because:


- It doubles the number of fragments processed.
- Lighting calculations are applied to both sides.

Use it only when necessary (e.g., thin surfaces like paper, leaves, flags, etc.).

`.fog` [See FOG for more details]



After making `.fog` false:



✓ Common Material Methods

Method	Description
<code>.clone()</code>	Returns a new material instance with the same properties.
<code>.copy(source)</code>	Copies properties from the <code>source</code> material to the current one.

Method	Description
<code>.dispose()</code>	Frees GPU memory. Call when you remove a material from the scene.
<code>.toJSON()</code>	Serializes the material to a JSON object (for exporting).
<code>.onBeforeCompile(shader)</code>	Hook to customize shader code before compiling (used with <code>ShaderMaterial</code> or advanced tweaking).
<code>.customProgramCacheKey()</code>	Used internally to differentiate cached shaders for material variants. Override if customizing shaders.
<code>.setValues(values)</code>	Applies an object of property values in bulk.

◆ Special Maps Used in Materials

Map Type	Purpose
<code>map</code>	Base color map (diffuse).
<code>normalMap</code>	Fake surface bumps by changing normals.
<code>bumpMap</code>	Older bump simulation, less accurate than <code>normalMap</code> .
<code>roughnessMap</code>	Controls how rough a surface is (used in PBR).
<code>metalnessMap</code>	Controls metallic parts (PBR).
<code>aoMap</code>	Ambient Occlusion for shadowy crevices.
<code>emissiveMap</code>	Adds self-glowing parts.
<code>displacementMap</code>	Actually moves vertices based on brightness.
<code>envMap</code>	Reflection map (used with reflective materials).

◆ Not all materials support all maps. For example, `MeshBasicMaterial` doesn't support lighting or normal maps.

◆ Common Usage Example

```
const texture = new THREE.TextureLoader().load('brick.jpg');

const material = new THREE.MeshStandardMaterial({
  color: 0xffffff,
  map: texture,
```

```
    roughness: 0.7,  
    metalness: 0.2,  
    side: THREE.DoubleSide  
  });  
  
const cube = new THREE.Mesh(new THREE.BoxGeometry(), material);  
scene.add(cube);
```

◆ Choosing the Right Material

Use Case	Material to Use
Fastest, unlit objects	<code>MeshBasicMaterial</code>
Realistic PBR lighting	<code>MeshStandardMaterial</code> / <code>MeshPhysicalMaterial</code>
Shiny plastic, classic lighting	<code>MeshPhongMaterial</code>
Soft matte with lights	<code>MeshLambertMaterial</code>
Cartoon-style rendering	<code>MeshToonMaterial</code>
Full shader customization	<code>ShaderMaterial</code>

◆ Modifying Material at Runtime

You can modify a material anytime:

```
mesh.material.color.set(0x00ff00);  
mesh.material.wireframe = true;  
mesh.material.opacity = 0.5;  
mesh.material.needsUpdate = true; // if changing something like side or wireframe
```

◆ Disposing Materials

To avoid memory leaks when removing a mesh:

```
mesh.geometry.dispose();  
mesh.material.dispose();  
scene.remove(mesh);
```

Color

THREE.Color is a class in **Three.js** used to represent and manipulate colors in the **RGB color space** . It plays a central role across Three.js, being used in materials, lights, backgrounds, and more.

THREE.Color — Overview

You can **create** , **set** , and **modify** a color in multiple formats:

- Hex (`0xff0000`)
- CSS-style string (`'red'` , `'#ff0000'` , `'rgb(255,0,0)'`)
- RGB (`new THREE.Color(1, 0, 0)`)

Creating a Color

```
const color1 = new THREE.Color(0xff0000);           // Hex
const color2 = new THREE.Color('skyblue');          // CSS color name
const color3 = new THREE.Color('#00ff00');          // CSS hex
const color4 = new THREE.Color(1, 0.5, 0);          // RGB values (range 0 to 1)
```

Properties

Property	Description
<code>.r</code>	Red component (0 to 1)
<code>.g</code>	Green component (0 to 1)
<code>.b</code>	Blue component (0 to 1)

Common Methods

Method	Description
<code>.set(value)</code>	Set color from another color, hex, CSS string, or RGB
<code>.setRGB(r, g, b)</code>	Set using RGB (0–1)
<code>.setHex(hex)</code>	Set from hex number
<code>.setHSL(h, s, l)</code>	Set from HSL (Hue 0–1, Saturation 0–1, Lightness 0–1)
<code>.getHex()</code>	Get hex representation
<code>.getStyle()</code>	Get CSS-style string

Method	Description
<code>.copy(color)</code>	Copy from another THREE.Color
<code>.clone()</code>	Clone the color
<code>.equals(color)</code>	Compare with another color
<code>.lerp(color, alpha)</code>	Linearly interpolate toward another color
<code>.add(color)</code>	Add RGB components from another color
<code>.multiply(color)</code>	Multiply RGB components with another color
<code>.convertSRGBToLinear()</code>	Convert sRGB to linear space
<code>.convertLinearToSRGB()</code>	Convert linear to sRGB
<code>.toArray()/.fromArray()</code>	Convert to/from RGB array

Examples:

Setting Color in Material

```
const material = new THREE.MeshStandardMaterial();
material.color = new THREE.Color(0xff8800);
```

Or modify it dynamically:

```
material.color.set('teal');
material.color.setRGB(0.2, 0.4, 0.8);
```

Example: Interpolating Between Two Colors

```
const color1 = new THREE.Color(1, 0, 0); // red
const color2 = new THREE.Color(0, 0, 1); // blue

color1.lerp(color2, 0.5); // halfway between red and blue
console.log(color1.getStyle()); // RGB string
```

Tip: Color Conversion

Three.js typically stores color values in **linear space** , but rendering in sRGB (gamma corrected) is common. You may want to use:

```
color.convertSRGBToLinear()
```

...if you're pulling colors from HTML/CSS sources.

✅ When to Use **THREE.Color**

- Material colors (**material.color**)
- Light colors (**light.color**)
- Scene background (**scene.background = new THREE.Color('#000')**)
- Fog, helper lines, shaders, etc.

Fog

THREE.Fog is a built-in class in **Three.js** used to simulate **atmospheric fog** , helping create depth, mood, and realism by fading objects based on their distance from the camera.

📦 Constructor Syntax

```
const fog = new THREE.Fog(color, near, far);
```

Parameter	Type	Description
color	THREE.Color or hex	The fog color (e.g., 0xcccccc)
near	Number	Distance from camera where fog starts
far	Number	Distance from camera where fog ends (beyond this, full fog color)

🔧 Example:

```
const scene = new THREE.Scene();  
scene.fog = new THREE.Fog(0x000000, 5, 20);
```

This means:

- At distance **5** , fog starts appearing.
- At distance **20** , objects are fully covered in fog color (black in this case).

Properties

Property	Description
<code>.name</code>	Optional string name
<code>.color</code>	<code>THREE.Color</code> object for fog color
<code>.near</code>	Start distance for fog to take effect
<code>.far</code>	End distance (full fog here)
<code>.isFog</code>	<code>true</code> (used internally for type checking)

Methods

Method	Description
<code>.clone()</code>	Creates a copy of the fog
<code>.toJSON()</code>	Serializes the fog to JSON

How It Works

Fog fades object colors to the fog color based on their distance from the camera, creating a **depth cue** . This is often used in:

- Outdoor environments (mist, haze)
- Stylized effects (low visibility, dreamy scenes)
- Performance optimization (limit what's visible at long distances)

Visual Representation

If `fog = new THREE.Fog(white, 1, 100)`:

- Distance < 1: No fog
- Distance = 50: 50% blend with white
- Distance ≥ 100: Fully white

Example 1:

```
const scene = new THREE.Scene();
scene.fog = new THREE.Fog(0xaaaaaa, 10, 50); // not scene.add()

const material = new THREE.MeshStandardMaterial({
  color: 0x3333ff,
  fog: true
});

const geometry = new THREE.BoxGeometry();
const mesh = new THREE.Mesh(geometry, material);
mesh.position.z = -30; // Inside fog range
scene.add(mesh);
```

Why `scene.add(fog)` not possible?

You **cannot** use `scene.add(fog)` in this case. Here's why:

 `Fog` in Three.js is **not** an `Object3D`

```
const fog = new THREE.Fog(0xaaaaaa, 10, 50);
scene.add(fog); // ❌ This will throw an error
```

`THREE.Fog` is **not** derived from `THREE.Object3D`, so it can't be added to the scene using `scene.add()` like lights or meshes.

 Correct Way

You must **assign** it directly to the `scene.fog` property:



```
scene.fog = new THREE.Fog(0xaaaaaa, 10, 50);
```


This is the proper way to enable fog in a scene.

 Why?

Three.js uses the `scene.fog` property during rendering to apply the fog effect to materials **that support fog** (like `MeshBasicMaterial`, `MeshStandardMaterial`, etc. with `fog: true`).

Example 2:






MeshLambertMaterial


`THREE.MeshLambertMaterial` is a material in **Three.js** that uses the **Lambertian reflectance model**, making it ideal for rendering **non-shiny, matte surfaces**. It reacts to lights (unlike `MeshBasicMaterial`) but **does not have specular highlights**, which makes it lightweight and efficient.


👉 Without light you won't see anything

With `AmbientLight`, won't feel any distinction with the faces:



But with PointLight, you will feel the distinction:





Constructor

```
const material = new THREE.MeshLambertMaterial([parameters]);
```

You can pass an optional object to configure properties.

Visual Character

-  Responds to lights ([PointLight](#), [DirectionalLight](#), etc.)
-  No shiny reflections or highlights
-  Supports **vertex colors**, **textures**, and **transparency**
-  Based on **Lambert lighting**, where brightness depends on the **angle between the surface normal and the light source**

Common Parameters

Here are the most commonly used properties of [MeshLambertMaterial](#):

Property	Type	Description
color	THREE.Color or hex	Diffuse color of the material

Property	Type	Description
map	Texture	Diffuse texture map
lightMap	Texture	Second set of UVs for baked lighting
aoMap	Texture	Ambient occlusion map
emissive	THREE.Color	Color the material emits (like a glow)
emissiveIntensity	Number	Intensity of emission
emissiveMap	Texture	Texture that controls emissive areas
transparent	Boolean	Enables transparency
opacity	Number	Opacity of the material
alphaMap	Texture	Alpha transparency map
wireframe	Boolean	Renders mesh as wireframe
vertexColors	Boolean or enum	Use vertex coloring
side	THREE.FrontSide (default), THREE.BackSide, or THREE.DoubleSide	
skinning	Boolean	For use with skinned meshes
morphTargets	Boolean	For morph targets (vertex animation)



Example:

```
const geometry = new THREE.BoxGeometry(1, 1, 1);
const material = new THREE.MeshLambertMaterial({
  color: 0x00ff00,
  emissive: 0x111111
});

const cube = new THREE.Mesh(geometry, material);
scene.add(cube);

// Add a light so Lambert can react
const light = new THREE.PointLight(0xffffff, 1);
light.position.set(2, 3, 4);
scene.add(light);
```

⚙️ Methods

All standard material methods are available:

🎨 Lighting Behavior

The color of a Lambert material depends on:

- The **angle** between the light direction and the surface normal
- The **color and intensity** of the light source
- The **material's base color and emissive values**

No **specular reflections** means the material appears soft and diffuse.

📦 Real-world Usage

Use `MeshLambertMaterial` when:

- You want **efficient, realistic-looking matte surfaces**
- You don't need shiny effects (use `MeshPhongMaterial` or `MeshStandardMaterial` instead)
- You're targeting **lower-performance devices** or large scenes

Examples:

- Walls, terrain, rocks, paper, unpolished wood

MeshPhongMaterial

MeshPhongMaterial is a material in Three.js that supports **specular highlights** and is ideal for rendering **shiny, glossy surfaces** . It uses the **Phong reflection model**, making it more visually rich than **MeshLambertMaterial**.

Constructor

```
const material = new THREE.MeshPhongMaterial(parameters);
```

You pass an object to configure various visual properties.

Key Features

-  **Responds to lights** (Point, Spot, Directional)
-  **Specular highlights** (shiny effects)
-  Supports **textures** , **transparency** , **vertex colors** , **fog** , etc.
-  **Efficient** for most realistic lighting use-cases
-  **Not physically based** (for that, use **MeshStandardMaterial** or **MeshPhysicalMaterial**)

Common Properties

Property	Type	Description
color	THREE.Color/ hex	Base/diffuse color of the material
specular	THREE.Color/ hex	Color of the specular highlights
shininess	Number	Size/strength of the specular highlight (default: 30)
emissive	THREE.Color/ hex	Color the material emits (glow)
emissiveIntensity	Number	Intensity of emission
emissiveMap	Texture	Controls emissive areas via texture
map	Texture	Diffuse/base color texture
specularMap	Texture	Per-pixel control of specular highlights

Property	Type	Description
<code>normalMap</code>	Texture	Surface detail using normals
<code>bumpMap</code>	Texture	Fake surface depth via grayscale
<code>bumpScale</code>	Number	Intensity of bump map
<code>displacementMap</code>	Texture	Moves vertices for real surface displacement
<code>displacementScale</code>	Number	Scale of displacement
<code>alphaMap</code>	Texture	Transparency mask
<code>transparent</code>	Boolean	Enables full transparency
<code>opacity</code>	Number	Sets opacity level
<code>wireframe</code>	Boolean	Renders mesh as lines
<code>vertexColors</code>	Boolean or enum	Enables per-vertex coloring
<code>flatShading</code>	Boolean	Enables flat (low-poly) shading
<code>fog</code>	Boolean	Material affected by scene fog

💡 Lighting Behavior

`MeshPhongMaterial` calculates lighting using:

- **Ambient**
- **Diffuse**
- **Specular** components

💡 What is a Specular Highlight ?

A **specular highlight** is the bright spot of light that appears on shiny objects when illuminated. It simulates the reflection of a **light source** directly into the viewer's eyes.

📷 Real-World Analogy

Think of:

- A shiny apple 🍏 reflecting a window's light
- A polished car hood 🚗 showing bright sun spots
- A ceramic mug ☕ with a white glint

That bright "glint" or "sparkle" is the **specular highlight** — it gives the **illusion of glossiness and shape** .

The specular highlight is controlled by **specular** and **shininess**. Higher **shininess** → smaller, sharper highlight.

Example

```
const geometry = new THREE.SphereGeometry(1, 32, 32);

const material = new THREE.MeshPhongMaterial({
  color: 0x156289,
  emissive: 0x072534,
  shininess: 100,
  specular: 0x111111
});

const sphere = new THREE.Mesh(geometry, material);
scene.add(sphere);

// Add light to see the Phong effect
const light = new THREE.PointLight(0xffffff, 1);
light.position.set(5, 5, 5);
scene.add(light);
```

Related Materials

Material	Specular Highlights	Physically Accurate	Notes
MeshBasicMaterial	✗	✗	No lighting
MeshLambertMaterial	✗	✗	Diffuse only
MeshPhongMaterial	✓	✗	Good for shiny look
MeshStandardMaterial	✓ (roughness/metalness)	✓	Better realism
MeshPhysicalMaterial	✓ + more	✓ ✓	Best for advanced realism

Inherits from `THREE.Material`, so it supports:

🔧 Real-World Use Cases

- Polished surfaces (e.g., ceramic, plastic, painted metal)
- Shiny UI elements (e.g., futuristic panels, buttons)
- Game objects that need a classic glossy look

Pane (From UI library- TweakPane)

Tweakpane is a **UI library** often used in conjunction with Three.js to build interactive **control panels** (for changing colors, values, toggles, etc.).

```
import { Pane } from 'tweakpane';

const pane = new Pane();

const params = {
  color: '#ff0000',
  speed: 1.5,
};

pane.addInput(params, 'color');
pane.addInput(params, 'speed', { min: 0, max: 5 });
```

🔧 Features of Pane:

- Easily create **sliders, checkboxes, color pickers, dropdowns** , etc.
- Good for live tweaking of object properties in DEVELOPMENT.
- Lightweight and customizable.
- Can group controls using folders.

Example Use Case:

Changing light intensity in Three.js:

```
const light = new THREE.PointLight(0xffffff, 1);
scene.add(light);

const pane = new Pane();
pane.addInput(light, 'intensity', { min: 0, max: 5 });
```

Why `params`?

In this code:

```
const params = {  
  color: '#ff0000',  
  speed: 1.5,  
};
```

 `params` is just a **container object** for values that we want to:

- Display and control in the **Tweakpane** UI.
- Dynamically update in our code (e.g., to change an object's color, speed, visibility, etc.)

 What's Happening:

When you write:

```
pane.addInput(params, 'speed');
```

Tweakpane:

- **Reads** `params.speed` and shows it as a **slider**.
- If you move the slider, it **automatically updates** `params.speed` in memory.
- You can then use `params.speed` inside your animation loop, for example:

```
cube.rotation.x += params.speed;
```

 Why use a `params` object and not just variables?

Imagine doing this instead:

```
let speed = 1.5;  
pane.addInput({ speed }, 'speed'); // This won't update `speed` outside!
```

That wouldn't work as expected because:

- Tweakpane creates its own internal copy of the object.

- Changing the slider wouldn't change your original `speed` variable.

But with an object like `params`, it's **passed by reference** , so:

- Any update in the pane reflects in `params.speed` immediately.
- You always use the **latest value** in your logic.

Use Case : Controlling a rotating cube's position, visibility, and rotation speed

```
import * as THREE from 'three';
import { Pane } from 'tweakpane';

const scene = new THREE.Scene();

const camera = new THREE.PerspectiveCamera(
  75,
  window.innerWidth / window.innerHeight,
  0.1,
  1000
);
camera.position.z = 5;

const renderer = new THREE.WebGLRenderer({ antialias: true });
renderer.setSize(window.innerWidth, window.innerHeight);
document.body.appendChild(renderer.domElement);

// 📦 Cube
const geometry = new THREE.BoxGeometry();
const material = new THREE.MeshNormalMaterial();
const cube = new THREE.Mesh(geometry, material);
scene.add(cube);

// 🛠️ Tweakpane Controls
const pane = new Pane();

const params = {
  speed: 0.01,
  visible: true,
  position: { x: 0, y: 0, z: 0 },
};

pane.addInput(params, 'speed', { min: 0, max: 0.1, step: 0.001 });
pane.addInput(params, 'visible').on('change', (ev) => {
  cube.visible = ev.value;
});
pane.addInput(params.position, 'x', { min: -5, max: 5 }).on('change', () => {
  cube.position.x = params.position.x;
});
pane.addInput(params.position, 'y', { min: -5, max: 5 }).on('change', () => {
  cube.position.y = params.position.y;
});
pane.addInput(params.position, 'z', { min: -5, max: 5 }).on('change', () => {
```

```
cube.position.z = params.position.z;
});

// 🔄 Animation Loop
function animate() {
  requestAnimationFrame(animate);

  cube.rotation.y += params.speed;
  cube.rotation.x += params.speed;

  renderer.render(scene, camera);
}

animate();
```

✅ Question:

Instead of `params.position` as the first parameter, wouldn't just `params` be fine?

🧠 Answer:

No, it wouldn't be functionally the same.

Here's why:

🔍 Tweakpane's `addInput()` expects:

```
pane.addInput(object, 'property')
```

Where:

- `object` is a **container object** holding the `property` you want to control.
- `property` is a key in that object (a string).

Your case:

```
const params = {
  position: { x: 0, y: 0, z: 0 }
};
```

So when you write:

```
pane.addInput(params.position, 'x')
```

You're **targeting** `params.position.x` directly — which is what you want for a slider controlling the x-position.

🔴 Why this won't work:

```
pane.addInput(params, 'x') // ❌ No such property!
```

- `params` does **not** have a property named `x`.
- It has a property named `position`, and inside that, there's `x`.

So this would throw an error or do nothing.

🔑 Here Why speed increased only inside `animate()` and not on `pane.addInput(...).on('change, ()=>...)` like others?

Here's the situation:

```
pane.addInput(params.position, 'x').on('change', () => {  
  cube.position.x = params.position.x;  
});
```

In this case:

- When the slider changes, the `.on('change', ...)` callback sets the position **once**, immediately.
- It updates a **static property** (`position.x`) directly.

✅ Why `.on('change', ...)` is enough for position:

Position is **static** — it doesn't change unless you explicitly update it. So you just need to set it **once** when the user moves the slider.

🔄 Now contrast that with **speed** :

In your animation loop:

```
function animate() {  
  cube.rotation.y += params.speed;  
  requestAnimationFrame(animate);  
}
```

- Here, `params.speed` is used every frame.
- So even though the slider changes `params.speed`, you don't need to use `.on('change', ...)` — because the **live value is being read continuously** inside `animate()`.

MeshStandardMaterial

★ The reason it's called the MeshStandardMaterial is it actually inherits a lot of different properties from industry standards and for that reason it's going to be pretty Hands-On

🚀 To understand the mesh standard material we first have to understand something called **PBR** and now PBR stands for Physically Based Rendering and it's basically a way to create 3D graphics and animations based on the principles of physics such as a law of light and materials to simulate the way that light interacts with different surfaces

So previously when we were using MeshLambert and MeshPhong those were different types of rendering models that tried to simulate the actual look and feel of lighting in different environments however PBR basically just takes it a step further and tries to apply different principles of physics into the actual look and feel of the end result

That's where the physical and physically based rendering comes from whereas MeshLambert and MeshPhong weren't necessarily physical approaches as they were more like mathematical approximations. The PBR workflow tries to simulate the way that something like roughness and metalness and how they interact with light in the real world to help you get closer to a realistic looking scene as if you were to see it in real life.

Now the best part about PBR is that it actually has become the industry standard in many 3D applications so here they provide us with **Unity** and **Unreal** which are both very popular game engines and then 3D Studio Max which is a type of 3D modeling software created by Autodesk which also makes Maya which is a very popular 3D modeling software for animations and also character animations as well. Blender also has its own implementation of PBR so because this is the standard across many different applications the types of properties that you're going to use in these 3D modeling softwares actually translates across into the mesh standard material.

So for example if I'm creating a PBR type of material in Blender and I actually export it as a glb and I bring it into 3GS, well the mesh standard material is actually going to recognize some of those channels and those channels being the metallic and the

roughness channels and it's actually going to display the actual model in 3GS very similar to the way that it looks within **Blender**

THREE.MeshStandardMaterial — In Detail

MeshStandardMaterial is one of the most physically accurate materials in Three.js. It supports **PBR (Physically Based Rendering)** , meaning it simulates realistic lighting by considering how real-world materials reflect and absorb light.

When to use:

Use **MeshStandardMaterial** when:

- You want **realistic-looking materials** (like metals, plastics, ceramics, etc.).
- You're using **lights** in the scene (especially directional, point, or spot lights).
- You want support for **roughness, metalness** , environment maps, and shadows.

Constructor Syntax:

```
const material = new THREE.MeshStandardMaterial({
  color: 0xaaaaaa,
  metalness: 0.5,
  roughness: 0.8,
});
```

Key Properties:

Property	Type	Description
color	THREE.Color	Base color of the surface.
roughness	Number(0 → 1)	Surface roughness. 0 = mirror-like, 1 = fully rough/diffuse.
metalness	Number(0 → 1)	How metallic the surface is. 1 = fully metal.
map	Texture	Diffuse (base color) texture.
roughnessMap	Texture	Overrides roughness using grayscale texture.

Property	Type	Description
<code>metalnessMap</code>	Texture	Overrides <code>metalness</code> using grayscale texture.
<code>normalMap</code>	Texture	Fake small surface detail without extra geometry.
<code>envMap</code>	CubeTexture	For environment reflections. Required for good metals.
<code>emissive</code>	Color	Light the material emits (e.g., for glowing effects).
<code>emissiveMap</code>	Texture	Texture for emissive areas.
<code>emissiveIntensity</code>	Number	Strength of emission.
<code>aoMap</code>	Texture	Ambient Occlusion map (grayscale).
<code>aoMapIntensity</code>	Number	Strength of ambient occlusion.
<code>displacementMap</code>	Texture	Displaces vertices (true geometry displacement).
<code>displacementScale</code>	Number	How much to displace.
<code>transparent</code>	Boolean	Enable transparency.
<code>opacity</code>	Number	Transparency level (0 → 1).
<code>wireframe</code>	Boolean	Renders mesh as wireframe.

Supported Maps:

 Texture maps supported by `MeshStandardMaterial`:

- `map`
- `normalMap`
- `roughnessMap`
- `metalnessMap`
- `aoMap`
- `displacementMap`
- `envMap`
- `emissiveMap`
- `alphaMap` (for transparency)

💡 Important Notes:

- You **must use lights** for this material to appear properly (unlike `MeshBasicMaterial`).
- **Environment maps** greatly enhance realism (especially for metals).
- Best used with **physically-correct lighting settings** (like `renderer.physicallyCorrectLights = true`).

🔧 Example:

```
const geometry = new THREE.SphereGeometry(1, 64, 64);

const material = new THREE.MeshStandardMaterial({
  color: 0x6699ff,
  metalness: 0.9,
  roughness: 0.2,
});

const sphere = new THREE.Mesh(geometry, material);
scene.add(sphere);
```

Add a light to see the effect:

```
const light = new THREE.DirectionalLight(0xffffff, 1);
light.position.set(5, 5, 5);
scene.add(light);
```

🧠 MeshStandardMaterial vs MeshPhongMaterial:

Feature	MeshStandardMaterial	MeshPhongMaterial
Physically based	✅ Yes	❌ No
Roughness/Metalness	✅ Yes	❌ No
Specular control	❌ No (<code>metalness</code> used instead)	✅ Yes
Realistic reflections	✅ Better	❌ Limited

MeshPhysicalMaterial

MeshPhysicalMaterial is an advanced extension of **MeshStandardMaterial** in Three.js, designed for **realistic, physically based rendering (PBR)** . It adds more sophisticated optical properties such as **clearcoat** , **transmission** , **index of refraction** , and **sheen** , enabling you to simulate materials like **glass, car paint, velvet, plastic** , and more with high fidelity.

 When to Use:

Use **MeshPhysicalMaterial** when you need:

- Realistic rendering of **transparent objects** (e.g., **glass, water**)
- **Car paint** or **lacquered surfaces** (with **clearcoat**)
- Materials with **soft surface reflections** like **silk or velvet** (with **sheen**)
- Control over **light refraction** , **thickness** , and **iridescence**

 Basic Syntax:

```
const material = new THREE.MeshPhysicalMaterial({
  color: 0xeeeeff,
  metalness: 0.3,
  roughness: 0.1,
  clearcoat: 1.0,
  clearcoatRoughness: 0.25,
  transmission: 1.0,
  thickness: 0.5,
});
```

 Extends **MeshStandardMaterial**

Everything in **MeshStandardMaterial** also works in **MeshPhysicalMaterial**, **plus** the following **additional properties** :

 Additional Properties (Only in **MeshPhysicalMaterial):**

Property	Type	Description
clearcoat	Float (0-1)	Adds a clear glossy layer (like car paint)
clearcoatRoughness	Float (0-1)	Roughness of the clearcoat layer
sheen	Color	Adds soft velvet-like surface reflection
sheenRoughness	Float (0-1)	Controls softness of sheen
sheenColor	Color	Color of sheen highlight

Property	Type	Description
<code>transmission</code>	Float (0-1)	Controls transparency (glass-like effect)
<code>thickness</code>	Float	Depth of material for refraction
<code>ior</code>	Float (default 1.5)	Index of Refraction (light bending)
<code>attenuationDistance</code>	Float	How far light travels through before being absorbed
<code>attenuationColor</code>	Color	Color of light absorbed while passing through
<code>iridescence</code>	Float (0-1)	Creates rainbow-like film effect
<code>iridescenceIOR</code>	Float	Controls strength of iridescence refraction
<code>specularIntensity</code>	Float	Intensity of specular highlight
<code>specularColor</code>	Color	Color of the specular reflection

💡 Example Use: Simulating Glass

```
const material = new THREE.MeshPhysicalMaterial({
  color: 0xffffffff,
  metalness: 0,
  roughness: 0,
  transmission: 1,
  thickness: 0.5,
  ior: 1.45,
  transparent: true,
});
```

Make sure to set `renderer.useLegacyLights = false` and `renderer.physicallyCorrectLights = true` for better realism.

🌈 Other Example: Car Paint with Clearcoat

```
const carPaint = new THREE.MeshPhysicalMaterial({
  color: 0xff0000,
  metalness: 0.8,
  roughness: 0.3,
  clearcoat: 1.0,
  clearcoatRoughness: 0.1,
});
```

Texture Maps It Supports:

Map Type	Purpose
<code>map</code>	Base color texture
<code>metalnessMap</code>	Controls metallic areas
<code>roughnessMap</code>	Controls roughness
<code>clearcoatMap</code>	Clearcoat strength
<code>clearcoatRoughnessMap</code>	Clearcoat blur
<code>sheenColorMap</code>	Velvet-like highlight
<code>transmissionMap</code>	Transparency control
<code>thicknessMap</code>	Refraction depth
<code>normalMap</code>	Surface detail
<code>envMap</code>	Reflections
<code>aoMap</code>	Ambient occlusion

Tips:

- `MeshPhysicalMaterial` is **heavier** on performance. Use only when necessary.
- Works best with **HDRI environment maps**.
- Transparent materials should have `transparent: true`.
- You can create **realistic glass, diamond, or plastic** using combinations of `transmission`, `thickness`, `ior`, and `attenuation`.

Differences vs `MeshStandardMaterial`:

Feature	<code>MeshStandardMaterial</code>	<code>MeshPhysicalMaterial</code>
Transmission / Refraction	❌ No	✅ Yes
Clearcoat Layer	❌ No	✅ Yes
Sheen / Velvet Effects	❌ No	✅ Yes
Index of Refraction	❌ No	✅ Yes
Iridescence	❌ No	✅ Yes

Scene - 2

In Three.js, the `THREE.Scene` class is the container for all your 3D content. Think of it as a **stage** where all objects (meshes, lights, cameras, etc.) are placed. It inherits from `THREE.Object3D`, so it comes with all the standard `Object3D` methods (like `add()`, `remove()`, `traverse()`), plus its own specific properties and uses.

`THREE.Scene` — Properties

Property	Type	Description
background	<code>Color</code> , <code>Texture</code> , <code>CubeTexture</code> , or <code>null</code>	Sets the background of the scene. You can use solid color or skybox.
environment	<code>Texture</code>	Used for environment mapping and lighting in physically based materials (PBR).
fog	<code>THREE.Fog</code> or <code>THREE.FogExp2</code>	Adds atmospheric fog to the scene.
overrideMaterial	<code>THREE.Material</code>	Force all objects in the scene to render using this material.
autoUpdate	<code>Boolean</code> (default: <code>true</code>)	Controls whether matrices are updated automatically.

Inherited from `Object3D`

Because `Scene` extends `Object3D`, it inherits **all** of these useful properties and methods:

Inherited Properties:

- `position`, `rotation`, `scale`
- `children`: array of objects added to the scene
- `matrix`, `matrixWorld`, `matrixAutoUpdate`
- `visible`, `name`, `type`
- `castShadow`, `receiveShadow`

`THREE.Scene` — Methods

Method	Description
add(object)	Adds a child object to the scene (mesh, camera, light, etc.)
remove(object)	Removes a child object
getObjectByName(name)	Searches the scene's hierarchy for an object with a given name
traverse(callback)	Recursively applies a function to the scene and all descendants
traverseVisible(callback)	Same as traverse , but skips invisible objects
getObjectById(id)	Retrieves an object by its internal Three.js ID
updateMatrixWorld(force)	Updates global world matrices
clear()	Removes all children from the scene (Three.js r160+ only)

Example:

```
const scene = new THREE.Scene();
scene.background = new THREE.Color(0xeeeeff);
scene.fog = new THREE.Fog(0xaaaaaa, 10, 50);

// Adding objects
const mesh = new THREE.Mesh(new THREE.BoxGeometry(), new
THREE.MeshStandardMaterial());
mesh.name = 'myBox';
scene.add(mesh);

// Access object
const found = scene.getObjectByName('myBox');

// Traverse all children
scene.traverse((child) => {
  console.log(child.type);
});
```

Advanced Usage:

- **scene.environment**: Used with **MeshStandardMaterial** or **MeshPhysicalMaterial** to provide **IBL (image-based lighting)** .
- **scene.overrideMaterial**: Useful for debugging (e.g., render all objects with wireframe).

Example--

```
Three.js 101 Crash Course: Beginner's Guide to 3D Web Design (7 HOURS!)
33 const sphere = new THREE.Mesh()
34 sphere.geometry = sphereGeometry
35 sphere.material = material
36 sphere.position.y = 1.5
37
38 const cylinder = new THREE.Mesh()
39 cylinder.geometry = cylinderGeometry
40 cylinder.material = material
41 cylinder.position.y = -1.5
42
43 // add the mesh to the scene
44 group.add(sphere, cylinder, cube, knot, plane)
45 scene.add(group);
46
47 // initialize the light
48 const light = new THREE.AmbientLight(0xffffff, 0.4);
49 scene.add(light);
50
51 const pointLight = new THREE.PointLight(0xffffff, 1.2);
52 pointLight.position.set(5, 5, 5);
53 scene.add(pointLight);
54
55 // initialize the camera
```

```
Three.js 101 Crash Course: Beginner's Guide to 3D Web Design (7 HOURS!)
81
82
83
84 // render the scene
85 const renderloop = () => {
86   group.children.forEach((child) =>{
87     if (child instanceof THREE.Mesh) {
88       child.rotation.y += 0.01
89     }
90   })
91
92   controls.update();
93   renderer.render(scene, camera);
94   window.requestAnimationFrame(renderloop);
95 };
96
97 renderloop();
98
```

Loading Texture

In Three.js, the **TextureLoader** is a built-in utility used to **load image files** as textures that can be mapped onto materials (e.g., for wrapping images around meshes like boxes, spheres, etc.).

✓ Syntax

```
const loader = new THREE.TextureLoader();

const texture = loader.load(
  'path/to/image.jpg', // URL to texture image
  function (texture) {
    // onLoad callback
    console.log('Texture loaded');
  },
  function (xhr) {
    // onProgress callback
    console.log((xhr.loaded / xhr.total) * 100 + '% loaded');
  },
  function (error) {
    // onError callback
    console.error('An error happened while loading texture');
  }
);
```

📁 Constructor

```
const loader = new THREE.TextureLoader([manager]);
```

- **manager** (*optional*) : An instance of `THREE.LoadingManager` to track and coordinate multiple loading processes.

🔑 Properties

Property	Description
<code>manager</code>	Reference to the <code>LoadingManager</code> being used.
<code>crossOrigin</code>	CORS setting (<code>''</code> , <code>'anonymous'</code> , <code>'use-credentials'</code>). For loading from external URLs.

🔑 Methods

Method	Description
<code>.load(url, onLoad, onProgress, onError)</code>	Loads a texture from the given URL.
<code>.setCrossOrigin(value)</code>	Sets the cross-origin mode.

Method	Description
<code>.setPath(path)</code>	Sets a base path to prepend to the URL.
<code>.setWithCredentials(value)</code>	Set whether credentials (cookies) are sent with requests.

Common Use Case Example

```
const textureLoader = new THREE.TextureLoader();
const texture = textureLoader.load('textures/brick_diffuse.jpg');

const material = new THREE.MeshStandardMaterial({
  map: texture
});

const geometry = new THREE.BoxGeometry(1, 1, 1);
const mesh = new THREE.Mesh(geometry, material);
scene.add(mesh);
```

Prepending Path

If you have multiple textures from the same directory:

```
const loader = new THREE.TextureLoader().setPath('/assets/textures/');
const texture1 = loader.load('wood.jpg');
const texture2 = loader.load('metal.jpg');
```

With LoadingManager

```
const manager = new THREE.LoadingManager();
manager.onStart = () => console.log('Loading started');
manager.onLoad = () => console.log('All textures loaded');

const loader = new THREE.TextureLoader(manager);
const texture = loader.load('img/stone.png');
```

Notes

- Image is loaded asynchronously, but the `load()` function **returns immediately** with a temporary texture object.
- Once the image finishes loading, the texture is updated automatically.

Supported Image Formats

- JPEG, PNG, GIF, WebP, etc.
- HDR & EXR (with specific loaders like [RGBELoader](#) or [EXRLoader](#)).

Combinations

You can combine [TextureLoader](#) with:

- **Bump maps** ([bumpMap](#))
- **Normal maps** ([normalMap](#))
- **Roughness/Metalness maps**
- **Alpha maps** ([alphaMap](#))
- **Displacement maps**